

PIPE UNDERDRAINS AND PIPE DRAIN SCHEDULE RAMPS IL 143								
LOCATION		SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE UNDER-DRAINS, 6"	PIPE UNDERDRAINS, 6" (SPECIAL)		CONCRETE HEADWALLS FOR PIPE DRAINS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTERS & SYMBOLS	OUTLET & HEADWALL STD. 601101
				FOOT				
STATION TO STATION		FOOT	FOOT	INSIDE	OUTSIDE	EACH	SQ FT	
RAMP I								
00+00.00	05+00.00	521	500		21	1	2	00+00
05+00.00	08+77.54	399	378		21	1	2	05+00
08+77.54	13+77.54	1039	1000	18	21	2	4	08+78
13+77.54	19+25.00	1134	1095	18	21	2	4	13+78
RAMP II								
01+00.00	08+34.88	1509	1470	18	21	2	4	08+35
08+34.88	11+87.51	744	705	18	21	2	4	11+88
11+87.51	16+87.51	521	500		21	1	2	16+88
16+87.51	21+87.51	521	500		21	1	2	21+88
21+87.51	22+87.56	121	100		21	1	2	22+88
RAMP III								
00+00.00	01+10.18	131	110		21	1	2	00+00
01+10.18	06+10.18	521	500		21	1	2	01+10
06+10.18	09+02.11	313	292		21	1	2	06+10
09+02.11	14+02.11	1039	1000	18	21	2	4	09+02
14+02.11	19+25.00	1085	1046	18	21	2	4	14+02
RAMP IV								
01+00.00	06+00.00	1039	1000	18	21	2	4	06+00
06+00.00	10+03.52	846	807	18	21	2	4	10+04
10+03.52	15+03.52	521	500		21	1	2	15+04
15+03.52	20+03.52	500	500					
20+03.52	21+35.15	153	132		21	1	2	21+35
SUBTOTAL		12656	12134	144	378	26	52	

SUMMARY OF PIPE UNDERDRAINS AND PIPE DRAIN SCHEDULE					
	SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE UNDERDRAINS 6"	PIPE UNDERDRAINS, 6" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS & SYMBOLS
	FOOT	FOOT	FOOT	EACH	SO FT
EB	91195	91340	4023	208	416
WB	90551	91038	3906	201	402
RAMPS	25125	24066	1059	53	106
TOTAL	206870	206443	8988	462	924

PIPE UNDERDRAINS AND PIPE DRAIN SCHEDULE RAMPS IL 4								
LOCATION		SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE UNDER-DRAINS, 6"	PIPE UNDERDRAINS, 6" (SPECIAL)		CONCRETE HEADWALLS FOR PIPE DRAINS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTERS & SYMBOLS	OUTLET & HEADWALL STD. 601101
				FOOT				
STATION TO STATION		FOOT	FOOT	INSIDE	OUTSIDE	EACH	SQ FT	
RAMP I (WB)								
1239+81.92	1244+00.00	439	418		21	1	2	1239+82
00+00.00	02+33.99	507	468	18	21	2	4	02+34
02+33.99	07+34.00	1039	1000	18	21	2	4	02+34
07+34.00	11+95.42	482	461		21	1	2	07+34
07+34.00	12+59.65	544	526	18		1	2	07+34
RAMP II (WB)								
01+25.31	05+00.00	788	749	18	21	2	4	05+00
05+00.00	10+00.00	1039	1000	18	21	2	4	10+00
10+00.00	15+00.00	521	500		21	1	2	10+00
15+00.00	20+00.00	521	500		21	1	2	15+00
RAMP III (EB)								
1205+00.00	1210+00.00	521	500		21	1	2	1210+00
1210+00.00	1214+92.57	514	493		21	1	2	1214+93
00+00.00	05+00.00	1039	1000	18	21	2	4	00+00
05+00.00	10+00.00	1039	1000	18	21	2	4	05+00
10+00.00	12+67.21	288	267		21	1	2	10+00
10+00.00	13+48.30	366	348	18		1	2	10+00
RAMP IV (EB)								
01+23.00	05+00.00	793	754	18	21	2	4	05+00
05+00.00	10+00.00	1039	1000	18	21	2	4	10+00
10+00.00	15+00.00	521	500		21	1	2	10+00
15+00.00	19+46.82	468	447		21	1	2	15+00
SUBTOTAL		12468	11931	180	357	27	54	