



COORDINATE TABLE			
STATION	OFFSET	NORTHING	EASTING
POT STA 12+06.30	0.00	765537.42	2413994.64
POT STA 12+38.13	0.00	765517.60	2413969.74
P.C. STA. 12+79.13	0.00	765492.07	2413937.66
P.I. STA. 13+39.11		765454.71	2413890.73
P.T. STA. 13+80.32	0.00	765400.72	2413916.86
P.C. STA. 15+30.13	0.00	765265.86	2413982.10
P.I. STA. 15+60.91		765238.16	2413995.51
P.T. STA. 15+89.84	0.00	765222.78	2414022.17
POT STA. 16+12.00	0.00	765211.72	2414041.37

PROP. CURVE PROPCKCL-1  
 PI STA. = 13+39.11  
 $\Delta$  = 77° 17' 59" (LT)  
 D = 76° 23' 40"  
 R = 75.00'  
 T = 59.98'  
 L = 101.19'  
 E = 21.03'  
 P.C. STA. = 12+79.13  
 P.T. STA. = 13+80.32

PROP. CURVE PROPCKCL-2  
 PI STA. = 15+60.91  
 $\Delta$  = 34° 12' 54" (LT)  
 D = 57° 17' 45"  
 R = 100.00'  
 T = 30.78'  
 L = 59.72'  
 E = 4.63'  
 P.C. STA. = 15+30.13  
 P.T. STA. = 15+89.84

FILE NAME =	USER NAME = hoffmanj	DESIGNED - DWB	REVISED -
c:\pwork\work\pwork\hoffmanj\0402244\xx	0876F13-sh1-ATB.DGN	DRAWN - DWB	REVISED -
*MODELNAME*	PLOT SCALE = 50.0000' / in.	CHECKED - CDL	REVISED -
	PLOT DATE = 6/27/2014	DATE - 5/7/14	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

CHANNEL RE-ESTABLISHMENT ALIGNMENT

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. 12+06.30 TO STA. 16+12.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-111,12/RS-3	MADISON	242	123
CONTRACT NO. 76F13				
ILLINOIS FED. AID PROJECT				