

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE ROADWAY	
				0005	RURAL
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	2195	2195	
40600990	TEMPORARY RAMP	SQ YD	1168	1168	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3276	3276	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3318	3318	
42400800	DETECTABLE WARNINGS	SQ FT	399	399	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	39549	39549	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	500	500	
44000600	SIDEWALK REMOVAL	SQ FT	3043	3043	
44200176	PAVEMENT PATCHING, TYPE I, 15 INCH	SQ YD	5	5	
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	61	61	
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	69	69	
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	1779	1779	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	760	760	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	373	373	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE ROADWAY	
				0005	RURAL
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	482	482	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	18	18	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5713	5713	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	962	962	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29490	29490	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	427	427	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	118	118	