

PAVEMENT MARKING SCHEDULE

LOCATION					PAINT PAVEMENT MARKING				THERMOPLASTIC PAVEMENT MARKING					TEMPORARY PAVEMENT MARKING					SHORT-TERM PAVEMENT MARKING (*)	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL					
					LINE 4"				LINE 12"	DOUBLE LINE 4"	LINE 4"	LINE 6"	LINE 24"	WHITE	YELLOW		WHITE										
					WHITE	YELLOW			YELLOW		WHITE			LET & SYM	LINE 12"	LINE 4"	LINE 4"	LINE 6"					LINE 24"	LET & SYM			
					SOLID	SKIP-DA SH	SOLID	LT/RT	SOLID	SOLID	SOLID	SOLID	SOLID		FOOT	FOOT	FOOT	FOOT					FOOT		SQ FT		
IL 148					FOOT	FOOT	FOOT		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	EACH	EACH								
121+03.	N	TO	120+24.65	N	157	20											24	66.6	1	1							
120+24.65	BK	=	120+36.29	AH																							
120+36.29	N	TO	52+00.	N	13673	1709											2,051	5810.8	85	85							
52+00.	N	TO	43+00.	N	1800	225	900	LT									270	1065.0	11	11							
43+00.	N	TO	41+30.	N	340	43											51	144.5	2	2							
41+30.	N	TO	31+75.	N	1910	239	955	RT									287	1130.1	12	12							
31+75.	N	TO	17+50.	N	2850	356											428	1211.3	18	18							
17+50.	N	TO	4+56.	N		324											388	237.2	16	16							
4+56.	N	TO	1+56.	N			84	1200			84	1200					3,852	1768.0	16	16							
1+56.	N	TO	0+44	N				200	112			34	36.4				200	112	34	36.4	1,038	554.4	9	9			
0+00	N	=	0+00	S																							
0+44	S	TO	1+56.	S				200	112			35	36.4				200	112	35	36.4	1,041	557.4	9	9			
1+56.	S	TO	4+56.	S				84	1200								84	1200			3,852	1768.0	16	16			
4+56.	S	TO	30+66.	S		653												653			783	478.5	33	33			
30+66.	S	TO	34+56.	S				109	1560									109	1560			5,007	2298.0	20	20		
34+56.	S	TO	35+56.	S					200	100									200	100		36.4	900	436.4	9	9	
36+88.	S	TO	37+88.	S					200	100									200	100		36.4	900	436.4	9	9	
37+88.	S	TO	41+78.	S	780				109	1560									109	1560	780		5,007	2558.0	20	20	
41+78.	S	TO	91+43.	S	9930	1241														1241	9930			1,490	4220.3	62	62
CROSSWALK AT 148/154 (N)																											
CROSSWALK AT 148/154 (S)																											
TOTALS					31439	4808	1855		386	6320	424	144	69	145.6	386	12983	31863	144	69	145.6	27,367	24,740.9	348	348			
PROJECT TOTALS					38103				386	6744	144	69	145.6	386	44847	144	69	145.6	27,367	24,741	348	348					

SOLID YELLOW LT/RT FOR NPZ'S SHALL BE ORIENTED LOOKING TO THE NORTH

- ONE APPLICATION EACH FOR HMA SURFACE REMOVAL, BINDER, AND SURFACE COURSE