

SUMMARY OF QUANTITIES

60B01

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A			J000-2A		X271-2A		Y007		Y030-1E		Y031-IF						Y031-3D		Y032-IF		
				SAUNDERS RD / FIELD DR ROADWAY			ROADWAY		IL RTE 60 BRIDGE		RETAINING WALL		LIGHTING		TRAFFIC SIGNALS						EMERGENCY VEHICLE PREEMPTION		TRAFFIC SURVEILLANCE		
				CPOA (FIELD DR.)	OPUS (SAUNDERS RD)	EDP	IL RTE 60/ I-94 RAMP		IL RTE 60 & I-94 RAMP/UNDERPASS				RIVERWOODS RD/BLVD		SAUNDERS RD / FIELD DR		I-94 RAMP/ INTERCONNECT		RIVERWOODS RD/BLVD / I-94 SB RAMP		SAUNDERS RD/ I-94 NB RAMP				
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	100% LAKE COUNTY	100% LAKE FOREST	100% LAKE COUNTY
20100110	TREE REMOVAL (6-15 UNIT DIAMETER)	UNIT	513		23		245	245																	
20100210	TREE REMOVAL (>15 UNIT DIAMETER)	UNIT	38				19	19																	
20101000	TEMPORARY FENCE	FOOT	600				300	300																	
20200100	EARTH EXCAVATION	CU YD	14035	233	672	595	6267.5	6267.5																	
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	6860				3430	3430																	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	19741	272	738	476	9127.5	9127.5																	
20400800	FURNISHED EXCAVATION	CU YD	70065				35032.5	35032.5																	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	734						367	367															
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	4185				2092.5	2092.5																	
20800150	TRENCH BACKFILL	CU YD	3135		19	13	1551.5	1551.5																	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	44756			1502	21627	21627																	
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	59480	409	1270	803	28499	28499																	
* 25000210	SEEDING, CLASS 2A	ACRE	5.25	0.25	0.25	0.25	2.25	2.25																	
* 25000300	SEEDING, CLASS 3	ACRE	5.25				2.625	2.625																	
* 25000312	SEEDING, CLASS 4A	ACRE	1.50				0.75	0.75																	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1127	23	23	23	529	529																	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1127	23	23	23	529	529																	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1127	23	23	23	529	529																	
* 25100630	EROSION CONTROL BLANKET	SQ YD	82406				41203	41203																	
* 25200100	SODDING	SQ YD	3948	409		78	1730.5	1730.5																	
* 25200200	SUPPLEMENTAL WATERING	UNIT	2966.0	20.0		5.0	1470.5	1470.5																	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	652	15	22	15	300	300																	
JS280150	TEMPORARY STABILIZATION WITH STRAW MULCH	ACRE	4.75				2.375	2.375																	
28000300	TEMPORARY DITCH CHECKS	EACH	57		3	6	24	24																	
28000500	INLET AND PIPE PROTECTION	EACH	14		5		4.5	4.5																	
28000510	INLET FILTERS	EACH	149	2	9	8	65	65																	
28100107	STONE RIPRAP, CLASS A4	SQ YD	206				103	103																	
28200200	FILTER FABRIC	SQ YD	206				103	103																	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	262				131	131																	
35300505	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/4"	SQ YD	158				79	79																	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	690	280	410																				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.6				2.3	2.3																	
40600300	AGGREGATE (PRIME COAT)	TON	31	2	6		11.5	11.5																	

* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 1 OF 12

SCALE: NONE DRAWN BY: CBS
DATE: MAY 8, 2007 CHECKED BY: MPG

06/28/2007 03:49:25 PM