F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	7
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60B01

SUMMARY OF QUANTITIES

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A SAUNDERS RD / FIELD DR ROADWAY			J000-2A ROADWAY		X271-2A		Y007		Y030-1E		Y031-1F										Y031-3D			Y032-1F
													LIGHTING		TRAFFIC SIGNALS										EMERGENCY VEHICLE PREEMPTION			TRAFFIC SURVEILLANCE
				CPOA (FIELD DR.)	OPUS (SAUNDERS RD.)	EDP	IL RTE 60/ I-94 RAMPS		IL RTE 60 BRIDGE		RETAINING WALL		IL RTE 60 & I-94 RAMPS/UNDERPASS		RIVERWOODS RD/BLVD			SAUNDERS RD / FIELD DR			I-94 RAMPS/ INTERCONNECT			RIVERWOODS RD/BLVD / I-94 SB RAMPS		SAUNDERS RD/ I-94 NB RAMPS	
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LIBERTY-VILLE F.D.	100% LINCOLN-SHIRE F.D.	100% LAKE FOREST	100% LAKE COUNTY
* 50200410	ROCK EXCAVATION FOR STRUCTURES (SPECIAL)	CU YD	150				75	75																				
50300225	CONCRETE STRUCTURES	CU YD	608.0						304.0	304.0																		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1154.0						577.0	577.0																		
50300260	BRIDGE DECK GROOVING	SQ YD	3186						1593	1593																		
50300280	CONCRETE ENCASEMENT	CU YD	32 ⚠1						16	16 ⚠1																		
50300300	PROTECTIVE COAT	SQ YD	5362						2681	2681																		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1						0.5	0.5																		
50500505	STUD SHEAR CONNECTORS	EACH	13860						6930	6930																		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	310100						155050	155050																		
50800515	BAR SPLICERS	EACH	1786						893	893																		
50901730	BRIDGE FENCE RAILING	FOOT	529						264.5	264.5																		
50901750	PARAPET RAILING	FOOT	295 ⚠1						147.5	147.5 ⚠1																		
51100100	SLOPEWALL, 4 INCH	SQ YD	1554						777	777																		
51201800	FURNISHING STEEL PILES HP 14X73	FOOT	7022						3511	3511																		
51202305	DRIVING PILES	FOOT	7022						3511	3511																		
51203800	TEST PILE STEEL HP 14X73	FOOT	3						1.5	1.5																		
51204650	PILE SHOES	EACH	130						65	65																		
51205200	TEMPORARY SHEET PILING	SQ FT	3670						1835	1835																		
51500100	NAME PLATES	EACH	1						0.5	0.5																		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	44						22	22																		
542A1063	PIPE CULVERTS, CLASS A, TYPE 2, 18"	FOOT	268				134	134																				
542A1069	PIPE CULVERTS, CLASS A, TYPE 2, 24"	FOOT	71				35.5	35.5																				
542A1075	PIPE CULVERTS, CLASS A, TYPE 2, 30"	FOOT	185				92.5	92.5																				
542A2749	PIPE CULVERTS, CLASS A, TYPE 4, 24"	FOOT	184				92	92																				
542A2761	PIPE CULVERTS, CLASS A, TYPE 4, 36"	FOOT	269				134.5	134.5																				
54213447	END SECTIONS, 12"	EACH	3				1.5	1.5																				
54213450	END SECTIONS, 15"	EACH	4				2	2																				
54213459	END SECTIONS, 24"	EACH	4				2	2																				
54213465	END SECTIONS, 30"	EACH	2				1	1																				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	12				6	6																				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	2				1	1																				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	EACH	2				1	1																				
54215412	CAST IN PLACE REINFORCED CONCRETE END SECTION - 12"	EACH	3				1.5	1.5																				

* - SPECIALTY ITEM

TY·LIN INTERNATIONAL

⚠ Rev. 7-25-07

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 3 OF 12

SCALE: NONE DRAWN BY: CBS

DATE: MAY 8, 2007 CHECKED BY: MPG