F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	12
STA. 432+83.12	TO STA. 470+56.84			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60B01

SUMMARY OF QUANTITIES

	IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	I000-2A SAUNDERS RD / FIELD DR ROADWAY			J000-2A ROADWAY		X271-2A		Y007		Y030-1E		Y031-1F TRAFFIC SIGNALS									Y031-3D			Y032-1F
					CPOA (FIELD DR.)	OPUS (SAUNDERS RD.)	EDP	IL RTE 60/ I-94 RAMPS		IL RTE 60 BRIDGE		RETAINING WALL		LIGHTING		RIVERWOODS RD/BLVD			SAUNDERS RD / FIELD DR			I-94 RAMPS/ INTERCONNECT		EMERGENCY VEHICLE PREEMPTION			TRAFFIC SURVEILLANCE
														IL RTE 60 & I-94 RAMPS/UNDERPASS										RIVERWOODS RD/BLVD / I-94 SB RAMPS	SAUNDERS RD/ I-94 NB RAMPS		
					100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LIBERTY-VILLE F.D.	100% LINCOLN-SHIRE F.D.	100% LAKE FOREST	100% LAKE COUNTY
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	40																9	9	2	10	10				
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1855										620	620	24.3	24.3	2.7	2.7				251.5	251.5				58
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2074												211.05	211.05	23.45	23.45	292.95	292.95	65.1	477	477				
*	JS811001	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA. GALVANIZED STEEL, PVC COATED	FOOT	20											20													
*	JS811002	CONDUIT ATTACHED TO STRUCTURE, 1" DIA. GALVANIZED STEEL, PVC COATED	FOOT	720											720													
*	81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	825						412.5	412.5																	
*	81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	201				25	25	75.5	75.5																	
*	81302000	JUNCTION BOX, CAST IRON, ATTACHED TO STRUCTURE, 4"X4"X3"	EACH	12											12													
*	81302300	JUNCTION BOX, CAST IRON, ATTACHED TO STRUCTURE, 12"X8"X6"	EACH	2											2													
*	81304100	JUNCTION BOX EMBEDDED IN STRUCTURE, 12" X 12" X 6"	EACH	4										2	2													
*	81400100	HANDHOLE	EACH	27												1.35	1.35	0.15	0.15	2.25	2.25	0.5	9.5	9.5				
*	81400200	HEAVY-DUTY HANDHOLE	EACH	6												0.45	0.45	0.05	0.05	0.90	0.90	0.2	1.5	1.5				
*	81400300	DOUBLE HANDHOLE	EACH	8												0.45	0.45	0.05	0.05	1.35	1.35	0.3	2	2				
*	81603170	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 8 GROUND, (EPR-TYPE RHW), 1" DIA. POLYETHYLENE	FOOT	9180										4590	4590													
*	81603195	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 2 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	60										30	30													
*	81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	3000											3000													
*	81700115	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 8	FOOT	125											125													
*	81700225	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 2-1/C NO. 6	FOOT	250											250													
*	81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	75											75													
*	81800415	AERIAL CABLE, 4-1/C NO. 6 WITH MESSENGER WIRE	FOOT	9185											9185													
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	14055										3832.5	3832.5	247.95	247.95	27.55	27.55	414.9	414.9	92.2	2263.5	2263.5				390
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	58										21	37													
*	JS821002	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	12											12													
*	JS830030	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	7											7													
*	JS830034	TEMPORARY WOOD POLE, 70 FT., CLASS 3, 15 FT. MAST ARM	EACH	12											12													
*	83050730	LIGHT POLE, ALUMINUM, 47.5 FT M.H., 8 FT. DAVIT ARM	EACH	14										7	7													
*	83050805	LIGHT POLE, ALUMINUM, 47.5 FT M.H., 12 FT. DAVIT ARM	EACH	26										13	13													
*	83057435	LIGHT POLE, WOOD, 80 FOOT, CLASS 3, WITH 15 FT MAST ARM	EACH	4											4													
*	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	311										148	148													15
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	36										18	18													
*	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SLAVAGED	EACH	14											14													

* - SPECIALTY ITEM

TY·LIN INTERNATIONAL

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 8 OF 12

SCALE: NONE — DRAWN BY: CBS

DATE: MAY 8, 2007 — CHECKED BY: MPG