F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	14
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60B01

SUMMARY OF QUANTITIES

	IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	I000-2A SAUNDERS RD / FIELD DR ROADWAY			J000-2A ROADWAY		X211-2A		Y007		Y030-1E		Y031-1F TRAFFIC SIGNALS									Y031-3D EMERGENCY VEHICLE PREEMPTION			Y032-1F
					CPOA (FIELD DR.)	OPUS (SAUNDERS RD.)	EDP	IL RTE 60/ I-94 RAMPS		IL RTE 60 BRIDGE		RETAINING WALL		LIGHTING IL RTE 60 & I-94 RAMPS/UNDERPASS		RIVERWOODS RD/BLVD			SAUNDERS RD / FIELD DR			I-94 RAMPS/ INTERCONNECT		RIVERWOODS RD/BLVD / I-94 SB RAMPS		SAUNDERS RD/ I-94 NB RAMPS	TRAFFIC SURVEILLANCE
					100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LIBERTY-VILLE F.D.	100% LINCOLN-SHIRE F.D.	100% LAKE FOREST	100% LAKE COUNTY
*	87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	175												20.25	20.25	2.25	2.25	54	54	12	5	5				
*	87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	105																			52.5	52.5				
*	87900200	DRILL EXISTING HANDHOLE	EACH	8												3.15	3.15	0.35	0.35				0.5	0.5				
*	88030020	SIGNAL HEAD, L.E.D., 1-FACE, 3 SECTION, MAST ARM MOUNTED	EACH	47												3.15	3.15	0.35	0.35	8.55	8.55	1.9	10.5	10.5				
*	88030050	SIGNAL HEAD, L.E.D., 1-FACE, 3 SECTION, BRACKET MOUNTED	EACH	22												0.9	0.9	0.1	0.1	2.25	2.25	0.5	7.5	7.5				
*	88030070	SIGNAL HEAD, L.E.D., 1-FACE, 4 SECTION, BRACKET MOUNTED	EACH	2																			1	1				
*	88030100	SIGNAL HEAD, L.E.D., 1-FACE, 5 SECTION, BRACKET MOUNTED	EACH	5												0.9	0.9	0.1	0.1				1.5	1.5				
*	88030110	SIGNAL HEAD, L.E.D., 1-FACE, 5 SECTION, MAST ARM MOUNTED	EACH	3												0.45	0.45	0.05	0.05				1	1				
*	88200110	TRAFFIC SIGNAL BACK PLATE, LOUVERED	EACH	50												3.6	3.6	0.4	0.4	8.55	8.55	1.9	11.5	11.5				
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	62												5.85	5.85	0.65	0.65	7.2	7.2	1.6	16.5	16.5				
*	88600100	DETECTOR LOOP, TYPE I	FOOT	2261												603	603	67	67	414.45	414.45	92.1						
*	88600300	DETECTOR LOOP, TYPE III	FOOT	2930																			1465	1465				
*	88700200	LIGHT DETECTOR	EACH	12																					2.5	2.5	7	
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	10																					2	2	6	
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	4			1									0.45	0.45	0.05	0.05				1	1				
*	89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	3												1.35	1.35	0.15	0.15									
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7836																			3316	3316				1204
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4			1									0.45	0.45	0.05	0.05				1	1				
*	89502380	REMOVE EXISTING HANDHOLE	EACH	40			9									2.25	2.25	0.25	0.25				13	13				
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	33			9									2.25	2.25	0.25	0.25				9.5	9.5				
*	X0325828	RELOCATE EXISTING SURVEILLANCE CAMERA, CABINET, AND POLE	EACH	3																								3
*	X0325829	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT & 52 FT	EACH	1																			0.5	0.5				
*	X0325830	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT & 55 FT	EACH	1																			0.5	0.5				
	X0325737	TEMPORARY TRAFFIC SIGNAL TIMINGS	EACH	4												0.45	0.45	0.05	0.05	0.45	0.45	0.1	1	1				
	X0325831	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 3"	SQ YD	7681				3840.5	3840.5																			
*	X0325832	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA. GALVANIZED STEEL, PVC COATED	FOOT	125										125														
	X4200534	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10" (SPECIAL)	SQ YD	672				336	336																			
	X0325833	WICK DRAINS	FOOT	18130				9065	9065																			
	X0325834	HORIZONTAL STRIP DRAINS	FOOT	2970				1485	1485																			
	JS120809	PVC DRAIN PIPE (8 IN.)	FOOT	454						227	227																	
*	A2006714	TREE, QUERCUS MACROCAPRA (BUR OAK), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	70				35	35																			
	X0320816	SLEEPER SLAB	SQ YD	295				147.5	147.5																			
	X0320870	BRACED EXCAVATION	CU YD	4424				2212	2212																			

* - SPECIALTY ITEM

TY·LIN INTERNATIONAL

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 10 OF 12

SCALE: NONE DRAWN BY: CBS

DATE: MAY 8, 2007 CHECKED BY: MPG

C:\DOCUMENTS AND SETTINGS\CBS\DESKTOP\60B01_SUMMARY OF QUANTITIES.DGN 05/08/2007 03:40:41 PM