## GENERAL NOTES - SEDIMENT AND EROSION CONTROL REQUIREMENTS:

- 1. EROSION CONTROL ITEMS ARE CONSIDERED TO BE HIGH PRIORITY ITEMS ON THIS CONTRACT. THE ENGINEER WILL IMPLEMENT ALL PROVISIONS OF THE SPECIFICATION NECESSARY TO ASSURE THAT EROSION CONTROL ITEMS ARE CONSTRUCTED AND MAINTAINED IN A TIMELY WAY ALL EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES, WHICH WILL POTENTIALLY CREATE ERODABLE CONDITIONS.
- 2. THE EROSION CONTROL MEASURES SHOWN ARE BUT A GRAPHICAL REPRESENTATION OF THE MINIMUM REQUIREMENTS. DEVIATIONS FROM THIS PLAN ARE TO BE EXPECTED AND ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER, LAKE COUNTY STORMWATER COMMISSION APPROVED DESIGNATED EROSION CONTROL INSPECTOR, OR GOVERNING AGENCY.
- 3. SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR, SITE CONDITIONS AND THE USE OF TEMPORARY OR PERMANENT MEASURES.
- 4. SOIL EROSION AND SEDIMENT CONTROL FEATURES SHALL BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF HYDROLOGIC DISTURBANCE OF UPLAND AREAS.
- 5. DISTURBED AREAS SHALL BE STABILIZED WITH TEMPORARY OR PERMANENT MEASURES WITHIN SEVEN DAYS OF THE END OF HYDROLOGIC DISTURBANCE OR REDISTURBANCE, REGARDLESS OF WEATHER CONDITIONS OR PROGRESS OF WORK.
- 6. AREAS OF EMBANKMENT HAVING SLOPES GREATER THAN OR EQUAL TO 3H:1V, AND APPROVED BY THE ENFORCEMENT OFFICER, SHALL BE STABILIZED WITH SOD, MAT, OR BLANKET IN COMBINATION WITH SEEDING.
- 7. EROSION CONTROL BLANKET SHALL BE REQUIRED ON ALL INTERIOR DETENTION BASIN SIDE SLOPES (WITHIN THE CONSTRUCTION LIMITS) BETWEEN NORMAL WATER LEVEL AND HIGH WATER LEVEL.
- 8. ALL STORM SEWERS THAT ARE OR WILL BE FUNCTIONING DURING CONSTRUCTION SHALL BE PROTECTED, BY AN APPROPRIATE SEDIMENT CONTROL MEASURE.
- 9. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.
- 10. ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES MUST BE MAINTAINED AND REPAIRED AS NEEDED. THE CONTRACTOR SHALL BE ULTIMATELY RESPONSIBLE FOR MAINTENANCE REPAIR.
- 11. A STABILIZED MAT OF AGGREGATE UNDERLAIN WITH FILTER CLOTH (OR OTHER APPROPRIATE MEASURE) SHALL BE LOCATED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION SITE TO OR FROM A PUBLIC RIGHT-OF-WAY, STREET, ALLEY OR PARKING AREA. ANY SEDIMENT OR SOIL REACHING AN IMPROVED PUBLIC RIGHT-OF-WAY, STREET, ALLEY OR PARKING AREA SHALL BE REMOVED BY SCRAPING OR STREET CLEANING AS ACCUMULATIONS WARRANT AND TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA.
- 12. SOIL STOCKPILES SHALL NOT BE LOCATED IN A FLOOD PRONE AREA OR DESIGNATED BUFFER PROTECTING WATERS OF THE UNITED STATES OR ISOLATED WATERS OF LAKE COUNTY.
- 13. IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION, DISCHARGES SHALL BE ROUTED THROUGH AN EFFECTIVE SEDIMENT CONTROL MEASURE (e.g. SEDIMENT TRAP, SEDIMENT BASIN, OR OTHER APPROPRIATE MEASURE.
- 14. SILT FENCE USED IN BOTH IDOT AND ISTHA JURIDICTION SHALL MEET MINIMUM AASHTO M288-00 STANDARDS.
- 15. THE USE OF HAY OR STRAW BALES SHALL NOT BE PERMITTED IN THE IMPLEMENTATION OF TEMPORARY DITCH CHECKS OR INLET AND PIPE PROTECTION.
- 16. THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NO. ILRIO, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGESFROM CONSTRUCTION SITE ACTIVITIES. NPDES PERMIT NO. ILR400493.

F.A.P. RTE.	SECTION	COUNTY		ſΥ	TOTAL SHEETS	SHEET NO.
335	119R-2		LAKE		439	132A
STA.	STA. 432+83.12 TO STA. 470+56.84					
FED. ROA	D DIST. NO.	ILLINOIS	FED.	AID F	ROJECT	

60B01

REVISION		ILLINOIS DEPARTMENT OF TRANSPORTATION						
NAME	DATE	TETTAOT2 DELM	TIMENT OF TRANSPOR	CIAITON				
		ILLINOIS	RTE 60 OVER	I-94				
			ROSION/SEDIMENT CO	NTROL:				
			ENERAL NOTES SHEET 1 OF 6					
		SCALE: NONE	DRAWN BY:	CBS				

DATE: MAY 8, 2007

CHECKED BY: DP