

PROPOSED SIGNING SCHEDULE

| SIGN NO. | ALIGNMENT | SIGN INFORMATION | | | | | | | | SUPPORT INFORMATION | | | | | SIGN DESCRIPTION | |
|----------|-----------------------|------------------|--------|----------------|----------|------|------------|-------------|-----------|---------------------|---------------|------------------|------------------------------|--|------------------|---|
| | | EX. STATION | OFFSET | PROP. STATION | OFFSET | TYPE | WIDTH (FT) | HEIGHT (FT) | AREA (FT) | TYPE | POST QUANTITY | POST LENGTH (FT) | BASE FOR TELES. STEEL (EACH) | STRUCTURAL STEEL SIGN SUPPOR-BREAKAWAY (POUND) | | CONCRETE FOUNDATIONS (CY) |
| | ILLINOIS 60 | | | 459+41.3 | 72.3' RT | 1 | 2 | 2.5 | 5 | MAST ARM | | | | | | R10-5 |
| | | | | SAME AS ABOVE | | 1 | 5 | 1.5 | 7.5 | | | | | | | ILL RTE 60 |
| | | | | SAME AS ABOVE | | 1 | 5 | 1.5 | 7.5 | | | | | | | ILL RTE 60 |
| | ILLINOIS 60 | | | 459+46.3 | 97.9' LT | 1 | 2.5 | 2.5 | 6.25 | SIGNAL POST | | | | | | R1-1 (FOLDING) |
| | ILLINOIS 60 | | | 459+46.3 | 97.9' LT | 1 | 2 | 2.5 | 5 | SIGNAL POST | | | | | | R10-5 |
| | ILLINOIS 60 | | | 460+49.4 | 67.1' RT | 1 | 2.5 | 2.5 | 6.25 | SIGNAL POST | | | | | | R1-1 (FOLDING) |
| | ILLINOIS 60 | | | 460+49.4 | 67.1' RT | 1 | 2 | 2.5 | 5 | SIGNAL POST | | | | | | R10-5 |
| | ILLINOIS 60 | | | 460+73.4 | 95.8' LT | 1 | 2 | 2.5 | 5 | MAST ARM | | | | | | R10-5 |
| | | | | SAME AS ABOVE | | 1 | 5 | 1.5 | 7.5 | | | | | | | ILL RTE 60 |
| | | | | SAME AS ABOVE | | 1 | 5 | 1.5 | 7.5 | | | | | | | ILL RTE 60 |
| | ILLINOIS 60 | | | 460+78.2 | 52.6' RT | 1 | 2 | 2.5 | 5 | MAST ARM | | | | | | R10-5 |
| | | | | SAME AS ABOVE | | 2 | 6 | 2.5 | 15 | | | | | | | FIELD DR (LEFT ARROW)/SAUNDERS RD (RIGHT ARROW) |
| | ILLINOIS 60 | | | 460+95.2 | 3.0' LT | 1 | 2 | 2.5 | 5 | TELESCOPING STEEL | 1 | 14.5 | | | | R4-7 |
| | | | | SAME AS ABOVE | | 1 | 2.5 | 3 | 7.5 | | | | | | | R3-5L |
| | ILLINOIS 60 | | | 461+05.0 | 69.7' LT | 1 | 2.5 | 2.5 | 6.25 | SIGNAL POST | | | | | | R1-1 (FOLDING) |
| | ILLINOIS 60 | | | 461+05.0 | 69.7' LT | 1 | 2 | 2.5 | 5 | SIGNAL POST | | | | | | R10-5 |
| | ILLINOIS 60 | | | 461+16.9 | 52.8' RT | 1 | 3 | 3 | 9 | WOOD SIGN SUPPORT | 1 | 15 | | | | W9-1R |
| | ILLINOIS 60 | | | 462+37.9 | 52.6' RT | 1 | 3 | 3 | 9 | TELESCOPING STEEL | 1 | 15 | | | | I-I107 "ADOPT A HIGHWAY GAMMA PHI OMEGA" |
| | | | | SAME AS ABOVE | | 1 | 3 | 3 | 9 | | | | | | | W21-I111 "CLEANUP CREW WORKING" (FOLDING SIGN) |
| | ILLINOIS 60 | | | 463+41.8 | 52.8' RT | 1 | 3 | 3 | 9 | WOOD SIGN SUPPORT | 1 | 15 | | | | W4-2R |
| | ILLINOIS 60 | | | 469+10.0 | 17.3' LT | 1 | 2 | 2.5 | 5 | TELESCOPING STEEL | 1 | 14.5 | | | | R4-7 |
| | ILLINOIS 60 | | | 470+04.5 | 1.40' RT | 1 | 2 | 2 | 4 | TELESCOPING STEEL | 1 | 14 | | | | R3-4 |
| | SB I-94 ENTRANCE RAMP | | | 120+66.3 | 26.0' RT | 2 | 3 | 4 | 12 | WOOD SIGN SUPPORT | 1 | 16 | | | | R-IT55 |
| | SB I-94 EXIT RAMP | | | 116+00.0 | 51.1' LT | 1 | 3 | 2 | 6 | WOOD SIGN SUPPORT | 1 | 14 | | | | R5-1A |
| | SB I-94 EXIT RAMP | | | 114+95.0 | 36.0' RT | 1 | 2 | 2 | 4 | WOOD SIGN SUPPORT | 1 | 14.5 | | | | D9-2 |
| | | | | SAME AS ABOVE | | 1 | 2 | 0.5 | 1 | | | | | | | D9-2A |
| | | | | SAME AS ABOVE | | 1 | 2.5 | 2.5 | 6.25 | | | | | | | R5-1A |
| | SB I-94 EXIT RAMP | | | 115+24.8 | 42.0' RT | 3 | 8 | 3 | 24 | WOOD SIGN SUPPORT | 2 | 36 | | | | D1-2 (LAKE FOREST/METTAWA) |
| | | | | SAME AS ABOVE | | 2 | 4.5 | 3 | 13.5 | | | | | | | "COLLEGES LAKE FOREST AND GRADUATE SCHOOL" |
| | SB I-94 EXIT RAMP | | | 114+34.9 | 33.7' LT | 1 | 3 | 3 | 9 | WOOD SIGN SUPPORT | 1 | 15 | | | | W3-3 |
| | SB I-94 EXIT RAMP | | | 114+20.5 | 32.6' RT | 1 | 3 | 3 | 9 | WOOD SIGN SUPPORT | 1 | 15 | | | | W3-3 |
| | SB I-94 EXIT RAMP | | | 114+06.7 | 32.5' RT | 2 | 4 | 2.5 | 10 | TELESCOPING STEEL | 2 | 29 | | | | R3-8 L/R |
| | NB I-94 EXIT RAMP | | | SIGN TO REMAIN | | | | | | | | | | | | EXISTING SIGN "EXIT & ARROW" |
| | NB I-94 EXIT RAMP | | | 194+90.0 | 17.0' RT | 1 | 2 | 2 | 4 | WOOD SIGN SUPPORT | 1 | 14 | | | | D9-2 |
| | | | | SAME AS ABOVE | | 1 | 2 | 0.5 | 1 | | | | | | | D9-2A |
| | NB I-94 EXIT RAMP | | | 195+71.5 | 17.6' RT | 1 | 3 | 3 | 9 | WOOD SIGN SUPPORT | 1 | 15 | | | | W3-3 |
| | NB I-94 EXIT RAMP | | | 195+72.3 | 64.0' LT | 1 | 3 | 3 | 9 | WOOD SIGN SUPPORT | 1 | 15 | | | | W3-3 |

NOTES:

- ALL RELOCATION WORK ON THIS SCHEDULE IS GOVERNED BY ARTICLE 107.25 UNLESS NOTED.
- REFER TO PROPOSED SIGNING PLANS FOR PROPOSED SIGN LOCATIONS.

TYLIN INTERNATIONAL

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94
PROPOSED SIGNING SCHEDULE
3 OF 3

SCALE: NONE
DATE: MAY 8, 2007

DRAWN BY: CBS
CHECKED BY: AMB