

CONTRACT NO. 60882

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	581EXT-BR	COOK	46	3
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES URBAN  
100% STATE

ENGLISH	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	IL 58 1000	IL 59 1000	BRIDGE X081-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	22	10	12	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	2	3	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	464	213	251	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1,083	497	586	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	99	51	48	
40600990	TEMPORARY RAMP	SQ YD	67	35	32	
42001300	PROTECTIVE COAT	SQ YD	839	839		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	749			749
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	91			91
44000100	PAVEMENT REMOVAL	SQ YD	430	430		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	11,136	5,174	5,962	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	404	404		
44003100	MEDIAN REMOVAL	SQ FT	5,725	5,725		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1			1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	55			55
50300260	BRIDGE DECK GROOVING	SQ YD	556.7			556.7
50300300	PROTECTIVE COAT	SQ YD	827.3			827.3
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	6,763			6,763
50800205	REINFORCING BARS, EPOXY COATED	POUND	16,100			16,100
50800515	BAR SPLICERS	EACH	105			105
51500100	NAME PLATES	EACH	1			1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	345	345		
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ FT	3,444	3,444		
60622000	CONCRETE MEDIAN, TYPE SM-2.12	SQ FT	1,361	1,361		
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	283	283		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	1	1		
63200310	GUARDRAIL REMOVAL	FOOT	490	490		
6700400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	2	2	6
67100100	MOBILIZATION	L SUM	1	0.2	0.2	0.6
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.2	0.2	0.6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	150	63	87	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	365	219	146	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18,257	17,446	811	

58700300	CONCRETE SEALER	SQ FT	304	30	30	504
44001005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	26	36	30	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES	SQ YD	392	216	176	
44201765	CLASS D PATCHES, TYPE II 10"	SQ YD	327	180	147	
44300200	STRIP REFLECTIVE CRAWL CONTROL TREATMENT	FOOT	5237	2394	2843	

\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAU 1320 (IL 58 GOLF ROAD) OVER POPLAR CREEK  SUMMARY OF QUANTITIES  DATE: 7/20/07 DRAWN BY: LT CHECKED BY: RS  GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC. CHICAGO, ILLINOIS
NAME	DATE	

Rev. 9-7-07 Rev.