

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2845	3152 WRS	COOK	195	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE													
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	M		CMM		M						NP		NP	
				80% FED. 20% STATE	80% FED. 17% PARK FOREST 3% CHICAGO HEIGHTS	80% FED. 10% STATE 10% PARK FOREST	80% FED. 13% STATE 6% PARK FOREST	80% FED. 20% STATE	80% FED. 13% STATE 6% PARK FOREST	80% FED. 15% STATE 5% PARK FOREST	80% FED. 20% STATE 5% PARK FOREST 5% CHICAGO HEIGHTS	80% FED. 20% STATE	100% PARK FOREST	80% STATE 19% PARK FOREST			
				1000-2A	Y030-1E	Y047	TRAFFIC SIGNALS MONEE ROAD	TRAFFIC SIGNALS SAUK TRAIL	TRAFFIC SIGNALS MAIN STREET	TRAFFIC SIGNALS NORWOOD BLVD	TRAFFIC SIGNALS NORWOOD PLAZA	TRAFFIC SIGNALS NORTH ST/ BEACAN BLVD	TRAFFIC SIGNALS ILLINOIS ST/16TH STREET	INTER-CONNECT	Y031-3D	Y007	
X8302397	LIGHT POLE, ALUMINUM, 25 FT. M. H., 15 FT. MAST ARM	EACH	1		1												
X8166794	UNIT DUCT WITH 4-1/C NO. 6 & 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 1.5" DIA POLYETHYLENE	FOOT	16918	14803	2115												
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	50	50													
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	230	230													
20101000	TEMPORARY FENCE	FOOT	3000	3000													
20101200	TREE ROOT PRUNING	EACH	20	20													
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10													
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	15	15													
20200100	EARTH EXCAVATION	CU YD	10191	10191													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12937	12937													
20400800	FURNISHED EXCAVATION	CU YD	1872	1872													
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	186	186													
20800150	TRENCH BACKFILL	CU YD	6128	6128													
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	33000	33000													
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	408	408													
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	408	408													
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	408	408													
25100630	EROSION CONTROL BLANKET	SQ YD	13552	13552													
25200110	SODDING, SALT TOLERANT	SQ YD	33000	33000													
25200200	SUPPLEMENTAL WATERING	UNIT	330	330													
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	500	500													
28000300	TEMPORARY DITCH CHECKS	EACH	20	20													
28000510	INLET FILTERS	EACH	180	180													
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	641	641													
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	4034	4034													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	40													
40600300	AGGREGATE (PRIME COAT)	TON	200	200													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	16	16													
40600895	CONSTRUCTING TEST STRIP	EACH	2	2													

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES	
NAME	DATE		

7/2/2007 10:42:00 AM