

F.A.U. R/E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2845	3152 WRS	COOK	195	12
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES				M		CMM		M										NP	NP
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE	80% FED. 17% PARK FOREST 3% CHICAGO HEIGHTS	80% FED. 10% STATE 10% PARK FOREST	80% FED. 13.7% STATE 6.3% PARK FOREST	80% FED. 20% STATE	80% FED. 13.7% STATE 6.3% PARK FOREST	80% FED. 15% STATE 5% PARK FOREST	80% FED. 20% STATE	80% FED. 5% PARK FOREST HEIGHTS	80% FED. 20% STATE	NP 100% PARK FOREST	NP 81% STATE 19% PARK FOREST				
				1000-2A	Y030-1E	Y047										Y031-3D	Y007		
					CITY OF CHICAGO HEIGHTS LIGHTING	VILLAGE OF PARK FOREST LIGHTING	VILLAGE OF PARK FOREST MULTI-USE TRAIL	TRAFFIC SIGNALS MONEE ROAD Y031-1F	TRAFFIC SIGNALS SAUK TRAIL Y031-1F	TRAFFIC SIGNALS MAIN STREET Y031-1F	TRAFFIC SIGNALS NORWOOD BLVD Y031-1F	TRAFFIC SIGNALS NORWOOD PLAZA Y031-1F	TRAFFIC SIGNALS NORTH ST/BEACAN BLVD Y031-1F	TRAFFIC SIGNALS ILLINOIS ST/16TH STREET Y031-1F	INTER-CONNECT Y031-1F	VILLAGE OF PARK FOREST TRAFFIC SIGNAL PREEMPTION	VILLAGE OF PARK FOREST OUTLET SEWER UPGRADES		
89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	2						2										
89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	2						2										
89501300	RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE	EACH	6						2			4							
89502215	MODIFY EXISTING CONTROLLER FOUNDATION	EACH	1					1											
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	36371				1134	553	4200	7743	3504	6391	5159	7687					
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	375					375											
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	7				1	1	1	1	1	1	1						
89502380	REMOVE EXISTING HANDHOLE	EACH	20											7					
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	37				1		4	9	7	8	8						
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	7	7															
A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6															
A2012001	TREE, AESCULUS X CARNE BRIOTTI (BRIOTTI HORSECHESTNUT), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6															
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	900	900															
X0322453	WEED CONTROL, PRE-EMERGENT	POUND	50	50															
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	290	290															
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	12100											12100					
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	360	360															
* X0323927	MAINTENANCE OF LIGHTING SYSTEM	EACH	1		1														
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	23684	23684															
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	3555	3555															
X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	141		123	18													
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11	11															
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	14	14															
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2090	2090															
* X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2						1				1						

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES