| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 2845 | 3152 WRS | COOK | 195 | 13 |
| FED. ROAD DIST. NO. 1 | ILLINOIS | HIGHWAY PROJECT | | |

## SUMMARY OF QUANTITIES

| | CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | I000-2A | CITY OF CHICAGO HEIGHTS LIGHTING | VILLAGE OF PARK FOREST LIGHTING | VILLAGE OF PARK FOREST MULTI-USE TRAIL | TRAFFIC SIGNALS MONEE ROAD | TRAFFIC SIGNALS SAUK TRAIL | TRAFFIC SIGNALS MAIN STREET | TRAFFIC SIGNALS NORWOOD BLVD | TRAFFIC SIGNALS NORWOOD PLAZA | TRAFFIC SIGNALS NORTH ST/ BEACAN BLVD | TRAFFIC SIGNALS ILLINOIS ST/16TH STREET | INTER-CONNECT | VILLAGE OF PARK FOREST TRAFFIC SIGNAL PREEMPTION | VILLAGE OF PARK FOREST OUTLET SEWER UPGRADES | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | M | | | CMM | M | | | | | | | | | | | | | |
| | | | | | 80% FED. 20% STATE | 80% FED. 17% PARK FOREST 3% CHICAGO HEIGHTS | | 80% FED. 10% STATE 10% PARK FOREST | 80% FED. 13.7% STATE 6.3% PARK FOREST | 80% FED. 20% STATE | 80% FED. 13.7% STATE 6.3% PARK FOREST | 80% FED. 15.4% STATE 5.4% PARK FOREST | 80% FED. 20% STATE | 80% FED. 10% STATE 5% PARK FOREST 5% CHICAGO HEIGHTS | | 80% FED. 20% STATE | 100% PARK FOREST NP | 81% STATE 19% PARK FOREST NP | | | | |
| | | | | | | Y030-1E | | Y047 | CONSTRUCTION TYPE CODE | | | | | | | | Y031-30 | Y007 | | | | |
| * | X8050015 | SERVICE INSTALLATION - POLE MOUNTED | EACH | 3 | | | | | 1 | 1 | | | | 1 | | | | | | | | |
| * | X8620020 | UNINTERRUPTIBLE POWER SUPPLY | EACH | 6 | | | | | 1 | 1 | 1 | 1 | | 1 | 1 | | | | | | | |
| * | X8710020 | FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F | FOOT | 13600 | | | | | | | | | | | | 13600 | | | | | | |
| * | X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 2535 | | | | | | | 402 | 1088 | | 585 | 460 | | | | | | | |
| * | X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED | FOOT | 1580 | | | | | | | | | | | | | 1580 | | | | | |
| * | X8950115 | RELOCATE LIGHT DETECTOR | EACH | 4 | | | | | | | 2 | 2 | | | | | | | | | | |
| * | X8950210 | REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE | EACH | 1 | | | | | | | | 1 | | | | | | | | | | |
| * | XX002066 | FLASHING BEACON AND FLASHER CONTROLLER | EACH | 1 | | | | | | 1 | | | | | | | | | | | | |
| * | XX002856 | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM | L SUM | 1 | | | | | | | | | | | | 1 | | | | | | |
| * | XX004861 | TREE, ULMUS CARPINIFOLIA ACCOLADE MORTON (ACCOLADE ELM), 2 1/2" CALIPER, BALLED AND BURLAPPED | EACH | 6 | 6 | | | | | | | | | | | | | | | | | |
| | Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 4935 | 4935 | | | | | | | | | | | | | | | | | |
| | Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| ▲ | Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 48 | 48 | | | | | | | | | | | | | | | | | |
| | Z0041700 | PLUG EXISTING STORM SEWERS | EACH | 7 | 7 | | | | | | | | | | | | | | | | | |
| | 54213675 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" | EACH | 1 | | | | | | | | | | | | | | 1 | | | | |
| ● | Z0076600 | TRAINEES | HOUR | 1500 | 1500 | | | | | | | | | | | | | | | | | |

▲ NON-PARTICIPATING
* SPECIALTY ITEMS
● Y080

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 7/2/2007

7/2/2007