

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2845	3152 WRS	COOK	195	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

WESTERN AVE.	EARTH EXCAVATION (CU. YD)	UNSUITABLE MATERIAL (CU.YD.)	EXCAVATION USED AS EMBANKMENT (SHRINKAGE 15%) (CU.YD.)	EMBANKMENT (CU. YD.)	EARTH WORK BALANCE SURPLUS (+) OR SHORTAGE (-) (CU. YD.)
219+10 TO 119+41	10191	12926	8662	6791	+1871

TREE REMOVAL SCHEDULE

STATION	OFFSET/ SIDE (FEET)	TYPE	6 TO 15 UNIT DIAMETER	OVER 15 UNIT DIAMETER
21+08	35.2' RT	HONEY LOCUST		18
22+92	35.6' RT	HONEY LOCUST		24
43+87	47.6' LT	SILVER MAPLE		18
44+18	48.1' LT	SILVER MAPLE		18
52+65	34.6' LT	SILVER MAPLE	14	18
55+51	30.0' LT	SILVER MAPLE		18
56+17	35.7' LT	SILVER MAPLE		18
58+70	36.1' LT	ASH		18
85+10	40.0 LT	SILVER MAPLE		16
85+10	40.0 RT	SILVER MAPLE	10	
85+30	40.0 LT	SILVER MAPLE		16
85+30	40.0 RT	SILVER MAPLE	12	
85+60	40.0 LT	SILVER MAPLE		16
85+60	40.0 RT	SILVER MAPLE	14	
85+85	40.0 LT	SILVER MAPLE		16
85+85	40.0 RT	SILVER MAPLE		16
TOTALS			50	230

NOTE:

A THICKNESS OF 12 INCHES OF TOPSOIL STRIPPING SHALL BE USED FOR REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

PLOT DATE = 6/21/2007
 FILE NAME = C:\p03000\03141619\design.dwg
 USER NAME = enerss

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**WESTERN AVE.
(16TH ST. TO STEGER.)
SCHEDULE OF QUANTITIES**

SCALE: VERT. _____
HORIZ. _____

DATE _____ DRAWN BY _____
CHECKED BY _____