

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	115(BR-1)	HANCOCK	44	5
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				I000	X080-2A
35101400	AGGREGATE BASE COURSE, TYPE B	TON	10	10	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	642	642	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	5	5	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.6	1.6	
40600300	AGGREGATE (PRIME COAT)	TON	8	8	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	575	575	
40600990	TEMPORARY RAMP	SQ YD	87	87	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	287	287	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	114	114	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	120	120	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	49	49	

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE: 05/02/07

DRAWN BY JCW
CHECKED BY JRB