

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	115(BR-1)	HANCOCK	44	6
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				I000	X080-2A
44000100	PAVEMENT REMOVAL	SQ YD	271	271	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	443	443	
48101300	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	TON	75	75	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	55	55	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	4.2		4.2
50300225	CONCRETE STRUCTURES	CU YD	5.4		5.4
50300260	BRIDGE DECK GROOVING	SQ YD	559	234	325
50300300	PROTECTIVE COAT	SQ YD	333		333
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2914		2914
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4780		4780

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY JCW
CHECKED BY JRB

DATE: 05/02/07

Rev.