



Notes:  
All structural steel shall conform to AASHTO Classification M-270 Gr. 36, unless otherwise noted.  
See Section 584 of the Standard Specifications for Epoxy Grouting of Threaded Rods. The cost of epoxy grouting threaded rods shall be included with Temporary Support System.  
Drilled holes shall miss existing reinforcement. Cut threaded rods, grind flush, and seal with epoxy after superstructure removal. Cost included with Temporary Support System.

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**TEMPORARY SUPPORT SYSTEM**  
IL ROUTE 9 OVER  
CAMP CREEK  
F.A.P. ROUTE 685 - SECTION 115 BR-1  
HANCOCK COUNTY  
STA. 607+43.00  
STRUCTURE NO. 034-0061

**REVISIONS**

NAME	DATE

**Lin Engineering, Ltd.**  
Consulting Engineers  
Chatham, Illinois

Designed By: DLS  
Checked By: MTH  
Date: 04/2007  
Files: 034-0061.dgn

Drawn By: AJP

7/2/2007 1:36:45 PM \$FILEABBREV\$