


**SUMMARY OF QUANTITIES**

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	STRUCTURAL X071-2A	CITY OF NAPERVILLE (100% NON-PARTICIPATING)
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	933		933	
X0324973	REMOVE AND REPLACE BITUMINOUS SURFACE, SPECIAL	SQ FT	6360			6360
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	28		28	
X0329891	SILT CURTAIN	SQ YD	76	76		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	1		2
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	1		3
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1	
XX000372	TEMPORARY AGGREGATE	TON	71	71		
XX000504	RESTORATION WORK	L SUM	1			1
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	250	85		165
XX004102	CONCRETE RIPRAP REMOVAL	SQ YD	14	14		
XX004238	BITUMINOUS DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	250			250
XX004804	CONDUIT IN TRENCH, TRANSITION	EACH	2			2
XX004809	UNDER BRIDGE CONDUIT SYSTEM	L SUM	1			1
XX005581	VIDEO TAPE	UNIT	1			1
XX005593	NEW SWITCH GEAR VAULT	EACH	4			4
XX005594	FA-2 ENCASEMENT	CU YD	200			200
XX005595	TRENCH BACKFILL, CA-6	CU YD	320			320
XX005596	CONNECTING TO EXISTING SWITCHGEAR VAULTS OR FUSE CANS	EACH	1			1
XX005597	ROD AND MANDREL	FOOT	12100			12100
XX005598	ADDITIONAL GROUND ROD INSTALLATION	EACH	5			5
XX005599	PULLING ROPE AND DETECTABLE MULE TAPE	FOOT	7000			7000
XX005600	COUNTERPOISE, UNPAVED	FOOT	250			250
XX005601	COUNTERPOISE, PAVED	FOOT	30			30
XX005602	HAND DIGGING, 0 FT TO 5 FT IN PAVEMENT	CU YD	20			20
XX005603	HAND DIGGING, 5 FT TO 20 FT IN PAVEMENT	CU YD	10			10
XX005604	HAND DIGGING, 0 FT TO 5 FT IN UNPAVED AREAS	CU YD	45			45
XX005605	HAND DIGGING, 5 FT TO 20 FT IN UNPAVED AREAS	CU YD	20			20
XX005612	HANDHOLE, DEH8	EACH	4			4
XX006223	PERIMETER EROSION BARRIER, MODIFIED	FOOT	830	830		
XX006444	MULCH, SPECIAL	ACRE	0.25			0.25
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	120		120	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		0.8	0.2
Z0030020	IMPACT ATTENUATORS, (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1		
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2		
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
Z0053700	RESETTING SURVEY MONUMENTS	EACH	1		1	
Z0076600	TRAINEES	HOUR	1,000	1,000		
X007052	CONDUIT RISER ASSEMBLY - 5 INCH	EACH	1			1
X007053	CONDUIT RISER ASSEMBLY - 6 INCH	EACH	2			2
X007054	HANDHOLE, DEH5	EACH	2			2
X007055	HANDHOLE, DEH6	EACH	3			3

Δ Y080

• - SPECIALTY ITEM

<table border="1"> <thead> <tr><th colspan="2">REVISIONS</th></tr> <tr><th>NAME</th><th>DATE</th></tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table>	REVISIONS		NAME	DATE							BRIDGE REHABILITATION BAILEY ROAD OVER WEST BRANCH OF THE DUPAGE RIVER  <b>SUMMARY OF QUANTITIES</b> (3 OF 3)	City of  <b>Naperville</b>	DRAWN: RTM CHECKED: SP APPROVED:	SHEET NO.  <span style="font-size: 2em;">5</span>
	REVISIONS													
	NAME	DATE												
DATE: JULY 13, 2007 SCALE: NONE														
CONSULTANT <b>TYLIN INTERNATIONAL</b>														
JOB NO.: C-91-062-04														
PROJECT NO.: BHM-8003(343)														