

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3509	00-00173-00-FP	COOK	246	7
STA.		TO STA.		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

PLOT DATE = 7/12/2007
 PLOT TIME = 9:05:00 AM
 PLOT SCALE = 3/4" = 1'-0"
 USER NAME = bjohnson

SUMMARY OF QUANTITIES				I000-2A ROADWAY WILMETTE 70% STU 30% STATE	I000-2A ROADWAY EVANSTON 70% STU 30% STATE	Y030-1E LIGHTING WILMETTE 70% STU 30% LA	Y030-1E LIGHTING EVANSTON 70% STU 30% LA	Y031-IF SIGNALS WESTERFIELD 70% STU 30% LA	Y031-IF SIGNALS LAKE 70% STU 30% LA	Y031-IF SIGNALS ISABELLA 70% STU 30% LA	Y003-TEA ENHANCEMENTS WILMETTE 80% ITEP 20% LA	Y060 WATER WILMETTE NON-PART 100% LA	Y060 WATER EVANSTON NON-PART 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY										
60500050	REMOVING CATCH BASINS	EACH	77	72	5								
60500060	REMOVING INLETS	EACH	20	14	6								
60500405	FILLING VALVE VAULTS	EACH	36										
60500705	CATCH BASINS TO BE FILLED TO MAINTAIN FLOW	EACH	1	1									
60600605	CONCRETE CURB, TYPE B	FOOT	2,418	1,788	630								
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	22,686	18,597	4,089								
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	360	360									
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	440	440									
60624600	CORRUGATED MEDIAN	SQ FT	32	32									
61139900	STORM SEWERS, SPECIAL 6"	FOOT	6,214	6,214									
63000000	• STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	38	38									
63100045	• TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4									
63100167	• TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2									
63200310	GUARDRAIL REMOVAL	FOOT	116	116									
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	870	870									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	16	2								
67100100	MOBILIZATION	L SUM	1	1									
70101700	• TRAFFIC CONTROL AND PROTECTION	L SUM	1	1									
70300100	• SHORT-TERM PAVEMENT MARKING	FOOT	21,250	19,206	2,044								
70300220	• TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	244,234	210,822	33,412								
70300280	• TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,620	1,140	480								
70300510	• PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	2,455	2,205	250								
70300520	• PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	15,195	8,145	7,050								
70300570	• PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	840	690	150								
70301000	• WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	19,610	16,257	3,353								
72000100	• SIGN PANEL - TYPE 1	SQ FT	1,142	858	285								
72400100	• REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	222	160	62								
72400310	• REMOVE SIGN PANEL - TYPE 1	SQ FT	575	575									
72400500	• RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	2	3								
72900100	• METAL POST - TYPE A	FOOT	635	431	204								
72900200	• METAL POST - TYPE B	FOOT	974	789	185								
78000100	• THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,622	2,254	368								
78000200	• THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26,160	22,613	3,547								
78000400	• THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	20,004	18,180	1,824								
78000600	• THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	351	304	47								
78000650	• THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	503	403	100								
78003110	• PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	656	612	44								
78003130	• PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	533	533									
78100100	• RAISED REFLECTIVE PAVEMENT MARKER	EACH	437	403	34								
78200410	• GUARDRAIL MARKERS, TYPE A	EACH	12	12									
78201000	• TERMINAL MARKER - DIRECT APPLIED	EACH	2	2									

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHERIDAN ROAD
 DATE 7/13/07
 DRAWN BY LTD
 CHECKED BY BJL