

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3509	00-00173-00-FP	COOK	246	13
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

PLOT DATE = 7/12/2007
 FILE NAME = g:\v\085\085\road\sheds\SCHED.dwg
 PLOT NAME = 83964.DWG / IN
 USER NAME = gschmidt

SCHEDULE OF DRIVES (CONTINUED)

STATION	OFFSET	TYPE	ADDRESS	EX/PR	44000200	X0656100	40603310	35501308	35501316	42300200	42300400	60600605	60603800	
				MATERIAL	DRV PVMT REM	DRV PVMT REM &	APP RATE	HMA SURF CSE, MIX "C" N50	HMA BASE CSE, 6"	HMA BASE CSE, 8"	PCC DRV PVMT, 6 INCH	PCC DRV PVMT, 8 INCH	CONC CURB, TY B	COMB CONC C&G, TY B-6.12
					SO YD	SO YD	(TON/SQ YD)	TON	SO YD	SO YD	SO YD	SO YD	FOOT	FOOT
SHERIDAN ROAD- RIGHT OFFSETS														
1006+27.4		RT	CE	1701	PCC							17		23
1007+77.4		RT	CE	1625 N	PCC							14		22
1009+23.9		RT	CE	1625 C	PCC							20		25
1011+14.6		RT	CE	1625 S	PCC							19		27
1012+22.1		RT	CE	PLAZA	PCC							35		44
		RT	CE	PLAZA	PAVERS			29						
1019+98.5		RT	PE	1437 - 1445	PCC						17			
1024+34.1		RT	PE	1325 N	PCC						12			
1024+69.2		RT	PE	1321 S	PCC						25			
1024+99.1		RT	PE	1321 S	PCC						0			
1025+36.8		RT	PE		PCC						27			
1025+72.2		RT	PE	1315 N	PCC						0			
1026+38.2		RT	PE	1315 S	PCC						12			
1029+86.7		RT	PE	1221	PCC						22			
1030+56.7		RT	PE	1213	PCC						17			
1031+06.2		RT	PE	1209	PCC						10			
1034+90.1		RT	PE	1129	PCC						20			
1035+66.6		RT	PE	1125	PCC						20			
1036+76.7		RT	PE	1111	PCC						20			
1040+66.1		RT	PE	1037 N	BIT		0.112	3	25					
1041+07.1		RT	PE	1033	BIT		0.112	3	22					
1042+00.7		RT	PE	1025 N	BIT		0.112	3	19					
1042+49.7		RT	PE	1025 S	BIT		0.112	3	22					
1042+90.9		RT	PE		PCC					19				
1049+24.1		RT	PE		BIT		0.112	3	21					
1050+03.9		RT	PE	921	BIT		0.112	3	22					
1050+44.4		RT	PE	915 N	BIT		0.112	3	23					
1050+72.6		RT	PE	915 S	BIT		0.112	3	23					
1051+32.2		RT	PE	911	BIT		0.112	3	21					
					STONE EDGE									
1054+22.0		RT	PE	849	PCC						24			
1055+05.7		RT	PE	845/843	PCC						33			
1055+89.7		RT	PE	835	BIT		0.112	3	22					
1056+71.1		RT	PE	829	BIT		0.112	4	27					
1066+67.9		RT	PE	701/699	BIT		0.112	21	182					
1067+00.4		RT	PE	701	BRICK									
1067+23.3		RT	PE	699	BRICK									
1067+84.0		RT	PE	693	PCC					20				
1069+25.5		RT	PE	687	PCC					18				
1071+49.9		RT	CE	CHANNEL	BIT		0.112	8	67					58
1076+75.1		RT	CE	BAHAI	BIT		0.112	4	34				50	
1080+26.0										9				
1086+68.7		RT	PE		PCC									
1087+25.9		RT	PE		BIT		0.112	3	24					30
1087+76.5		RT	PE		BIT		0.112	2	11					
1095+90.9		RT	PE		BIT		0.112	2	11					
1096+37.8		RT	PE		BIT		0.112	2	12					
1097+57.9		RT	CE	2808		7								
1098+15.6		RT	CE	2808	BIT		0.112	3	21					
1101+12.0		RT	PE		BIT		0.112	0	0					
SUBTOTAL (RIGHT OFFSETS)					737	64		79	487	122	325	105	191	88
ISABELLA STREET														
4090+50.1		LT	PE		PCC						21			
4090+69.6		RT	PE		PCC						21			
4094+69.3		LT	PE		PCC						21			
4094+67.6		RT	PE		PCC						21			
4097+68.8		LT	PE		PCC						21			
4097+84.2		LT	CE		PCC						21			
4098+03.7		LT	PE		PCC						21			
4097+84.6		RT	CE		PCC						21			
4098+04.1		RT	PE		PCC						21			
4100+74.5		RT	PE		PCC						21			
4101+30.0		RT	PE		PCC						21			
4101+30.3		LT	CE		PCC						21			
4101+62.4		LT	CE		PCC						21			
4101+54.1		RT	PE		PCC						21			
4103+90.8		RT	PE		PCC						21			
4104+14.0		RT	PE		PCC						21			
SUBTOTAL (ISABELLA ST.)					329	0	0	0	0	252	84	0	0	0
LAKE AVENUE														
3049+53.7		LT	CE		BIT		0.112	4	31					41
3050+31.7		LT	PE		PCC						21			
3049+38.7		RT	PE		BIT		0.112	4	27					
3050+23.2		RT	PE		PCC						24			
3050+51.8		RT	PE		BRICK						22			
SUBTOTAL (LAKE AVENUE)					104	22		8	27	31	45	0	0	41
CHESTNUT SOUTH					22						21			
SUBTOTAL (OTHER)					22	0		0	0		21	0	0	0
TOTALS					2,740	181		116	688	180	1,534	775	708	182

1051 PERIMETER DRIVE, SUITE 1025
 SCHAMBERG, ILLINOIS 60173
 (847) 605-9600



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SHERIDAN ROAD
 DATE 7/13/07
 DRAWN BY LTD
 CHECKED BY BJL
 NO SCALE