

MUNICIPALITY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
QUINCY	06-00300-00-LS	ADAMS	69	5

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

ITEM	UNIT	TOTAL	CONSTRUCTION CODE TYPE	CONSTRUCTION CODE TYPE	CONSTRUCTION CODE TYPE
			I000	Y030 (2)	Y031 (2)
44000500 COMBINATION CURB AND GUTTER REMOVAL	FOOT	570	570		
44000600 SIDEWALK REMOVAL	SQ FT	46954	46954		
44004400*PAVEMENT REMOVAL (SPECIAL)	SQ YD	505	505		
44004700*SIDEWALK REMOVAL (SPECIAL)	SQ FT	788	788		
50100100*REMOVAL OF EXISTING STRUCTURES	EACH	2	2		
55019500 STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS IV 12"	FOOT	71	71		
55021600 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS III 12"	FOOT	138	138		
551B0300*STORM SEWER INSTALLATION, CLASS B 8"	FOOT	33	33		
55100300 STORM SEWER REMOVAL 8"	FOOT	53	53		
55100500 STORM SEWER REMOVAL 12"	FOOT	56	56		
(2) 56103800*DUCTILE IRON WATER MAIN, MECHANICAL JOINT 6"	FOOT	34	34		
(2) 56400100 FIRE HYDRANTS TO BE MOVED	EACH	1	1		
(2) 56500300*DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	1	1		
(2) 56500600*DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	45	45		
59300100 CONTROLLED LOW STRENGTH MATERIAL	CU YD	24			24
60218400 MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60242820 INLETS, SPECIAL, TYPE E	EACH	9	9		
(1) 60255500 MANHOLES TO BE ADJUSTED * SEE SPECIAL PROVISIONS	EACH	25	25		

(1) NON-PARTICIPATING ITEM FOR TRANSPORTATION ENHANCEMENT FUNDING

(2) SPECIALTY ITEMS

SUMMARY OF QUANTITIES
SHEET 2 OF 7

PLT DATE = 5/2/2007
PLT SCALE = 40.0000 / IN
USER NAME = default