

MUNICIPALITY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
QUINCY	06-00300-00-LS	ADAMS	69	9

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				I000	Y030 (2)	Y031 (2)
	88102810*PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	22			22
	88200100 TRAFFIC SIGNAL BACKPLATE	EACH	39			39
	89502350 REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1368		553	815
	89502375*REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4			4
	89502380 REMOVE EXISTING HANDHOLE	EACH	10			10
	89502385*REMOVE EXISTING CONCRETE FOUNDATION	EACH	3			3
	XX001607*RETAINING WALL, SPECIAL	SQ FT	45	45		
(2)	XX003120*YARD HYDRANT (FROST PROOF)	EACH	1	1		
	XX003436*RELOCATE SIGN PANEL - TYPE 1	EACH	23	23		
	XX004047*LIGHTING CONTROLLER, SPECIAL	EACH	1		1	
	XX004051*LIGHT POLE, ORNAMENTAL	EACH	78		78	
	XX004052*LUMINAIRES, ORNAMENTAL	EACH	81		81	
	XX005240*SIDEWALK REMOVAL - VAULTED	SQ FT	801	801		
	XX005317*GRANULAR STRUCTURAL FILL	CU YD	314	314		
	XX006429*SIDEWALK, SPECIAL	SQ FT	788	788		
	X0301059*BLOCK RETAINING WALL	SQ FT	446	446		
(1)	X0321766*LIGHT POLE, SPECIAL (DECORATIVE ORNAMENTAL)	EACH	1			1
	X0322121*SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	134	134		
	X0322683*CONCRETE FOUNDATION 24" DIA.	FOOT	231		231	
	X0323153*ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6, 1C (GREEN)	FOOT	2376			2376
	* SEE SPECIAL PROVISIONS					

(1) NON-PARTICIPATING ITEM FOR TRANSPORTATION ENHANCEMENT FUNDING

(2) SPECIALTY ITEMS

SUMMARY OF QUANTITIES
SHEET 6 OF 7