

FILE NAME * S:\JDL\6388--6394\6346\023\micross\Sheet\0108132-sh.txd

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE													
				80% FED. 20% STATE	80% STATE 20% MONT-GOMERY	80% STATE 20% OSWEGO	80% FED. 20% STATE	80% FED. 10% STATE 5% MONT-GOMERY 5% OSWEGO TOWNSHIP	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	100% MONT-GOMERY	50% OSWEGO 50% MONT-GOMERY	80% FED. 20% STATE	80% FED. 20% STATE	100% OSWEGO		
				ROADWAY	SIDEWALK	SIDEWALK	BRIDGE REPLACEMENT S. N. 047-0301	BRIARCLIFF	DOUGLAS	FIFTH	GOODWIN DR.	STREET LIGHTING	NOISE ABATEMENT WALLS	WATER MAIN			
				0003	0021	0021	0010	TRAFFIC SIGNALS - 0021			0021	0040	0043	0043			
URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN					
+ X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	5										5				
+ X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8'	EACH	2										2				
+ X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1								1						
+ X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1							1							
+ X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	3					1	1	1							
+ X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	2,312							** 1,156	** 1,156						
+ X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,513							•689		824					
+ XX000836	PRESSURE TESTING AND DISINFECTION	L SUM	1													1	
+ XX004622	REMOVAL OF LUMINAIRE, SALVAGE	EACH	4										4				
+ XX004731	CONNECTION TO EXISTING WATERMAIN	EACH	2													2	
Z0004552	APPROACH SLAB REMOVAL	SQ YD	131	131													
+ Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1													
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	4					4									
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4													

+ SPECIALTY ITEM • 100% OSWEGO **Δ 100% STATE** **** 80% FED./20% STATE**



1170 SOUTH HARBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = amandaj	DESIGNED -	REVISED -
	PLOT SCALE = 20.0000' / 1"	DRAWN -	REVISED -
	PLOT DATE = 5/14/2012	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE. 349	SECTION 11 WRS-3	COUNTY KENDALL	TOTAL SHEETS 527	SHEET NO. 30
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.

CONTRACT NO. 60132