

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE														
				80% FED. 20% STATE	80% STATE 20% MONT-GOMERY	80% STATE 20% OSWEGO	80% FED. 20% STATE BRIDGE REPLACEMENT S.N. 047-0301	80% FED. 10% STATE 5% MONT-GOMERY 5% OSWEGO TOWNSHIP	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	100% MONT-GOMERY	50% OSWEGO 50% MONT-GOMERY	80% FED. 20% STATE	80% FED. 20% STATE	100% OSWEGO			
				ROADWAY 0003	SIDEWALK 0021	SIDEWALK 0021	047-0301	BRIARCLIFF	DOUGLAS	FIFTH	GOODWIN DR.	STREET LIGHTING 0021	NOISE ABATEMENT WALLS 0040	WATER MAIN 0043				
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN			
Z0026407	TEMPORARY SHEET PILING	SO FT	1.948	914			1.034											
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	8	8														
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	8	8														
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	127	127														
+ Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	14										14					
+ Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6										6					
+ Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1							**	1							
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	9.047	9.047														
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	355				355											
Z0056644	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 8"	FOOT	12	12														
Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	15	15														
Z0062456	TEMPORARY PAVEMENT	SO YD	27,348	27,348														
+ Z0065100	SETTLEMENT PLATFORMS	EACH	5				5											
Z0068200	STEEL CASINGS 30"	FOOT	188													188		

FILE NAME : S:\JUL16328-6294\63161823\MicroStation\0180132-plt.psdgn

+ SPECIALTY ITEM • 100% OSWEGO **** 80% FED./20% STATE**



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME : amanda	DESIGNED -	REVISED -
PLDT SCALE : 28.0000' / 1"	CHECKED -	REVISOR -	REVISOR -
PLDT DATE : 5/14/2012	DATE -	REVISOR -	REVISOR -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 349	SECTION 11 WRS-3	COUNTY KENDALL	TOTAL SHEETS 527	SHEET NO. 31
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60132	

Rev.