

SCHEDULE OF TEMPORARY CONCRETE BARRIER

FROM STATION	TO STATION	LT/RT	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 2 (EACH) (Z0030240)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 2 (EACH) (Z0030340)	TEMPORARY CONCRETE BARRIER (FT) (70400100)	RELOCATE TEMPORARY CONCRETE BARRIER (FT) (70400200)
US ROUTE 30						
PRE-STAGE						
343+08.73		RT	1			
343+35.16	344+47.46	RT			113	
344+74.33		RT	1			
STAGE 1						
343+08.73		RT	1			
343+35.16	344+47.46	RT			113	
344+74.33		RT	1			
STAGE 2						
311+10.50		LT		1		
311+41.50	315+89.20	LT/RT			448	
315+89.20	339+29.00	RT			2,340	
339+51.87		RT		1		
340+39.40		RT	1			
340+65.59	350+40.73	RT			1,087	
350+40.73	351+53.07	RT				113
351+76.17		RT	1			
398+09.37		LT	1			
398+35.00	399+35.00	LT			100	
399+54.80		LT	1			
STAGE 2						
397+79.01		LT		1		
398+05.25	399+05.29	LT				100
399+21.77		LT		1		
418+79.67		LT		1		
419+05.38	421+42.88	LT				238
421+60.71		LT		1		
419+31.87		LT		1		
419+58.13	421+95.83	LT				238
422+10.91		LT		1		
TOTAL			8	8	4,201	688

SCHEDULE OF HIGH-EARLY STRENGTH PCC PAVEMENT 9 1/2" (JOINTED)

STAGE	INTERSECTION	HIGH-EARLY STRENGTH PCC PAVEMENT 9 1/2" (JOINTED) (SQ YD) X4201000
US ROUTE 30		
1	DOUGLAS	266
1	FIFTH	223
STAGE 2		
2	DOUGLAS	453
2	FIFTH	516
2	GOODWIN	281
TOTAL		1739

SCHEDULE OF STORM SEWERS TO BE CLEANED

FROM STATION	OFFSET (FT)	TO STATION	OFFSET (FT)	STORM SEWERS TO BE CLEANED, 18" (FT) X5538000	STORM SEWERS TO BE CLEANED, 24" (FT) X5538200		
US ROUTE 30							
306+49.36	48.81	LT	307+00.73	48.16	LT	51	
307+00.73	48.16	LT	307+02.22	35.12	LT	13	
307+00.73	48.16	LT	307+32.13	48.32	LT	31	
308+36.13	34.52	LT	309+37.04	37.08	LT	101	
309+37.04	37.08	LT	310+96.54	35.58	LT	160	
310+96.54	35.58	LT	311+61.68	34.28	LT	65	
352+10.00	50.00	RT	352+10.00	-46.00	LT	96	
373+22.82	51.02	RT	374+80.73	50.79	RT	158	
373+23.09	47.41	RT	374+80.83	47.47	RT	158	
384+10.00	56.00	RT	384+10.00	-36.00	LT	92	
395+17.00	66.00	RT	395+17.00	-60.00	LT	126	
TOTAL						222	829

SCHEDULE OF AGGREGATE SUBGRADE IMPROVEMENT

FROM STATION	TO STATION	OFFSET	AGGREGATE SUBGRADE IMPROVEMENT (CU YD) 30300001
US ROUTE 30			
332+50.00	338+50.00	LT	692
332+50.00	338+50.00	RT	692
350+25.00	353+50.00	LT	375
350+25.00	353+50.00	RT	375
365+25.00	365+50.00	LT	15
365+50.00	371+25.00	LT	332
365+25.00	369+38.00	RT	238
369+38.00	371+25.00	RT	127
371+25.00	374+25.00	LT	346
371+25.00	371+38.00	RT	21
371+38.00	374+25.00	RT	461
377+25.00	378+84.00	LT	510
378+84.00	380+25.00	LT	410
377+25.00	380+25.00	RT	692
386+25.00	389+25.00	LT	173
386+25.00	389+25.00	RT	173
407+25.00	410+25.00	LT	173
407+25.00	410+25.00	RT	173
425+75.00	428+75.00	LT	346
425+75.00	427+79.97	RT	237
427+79.97	428+20.53	RT	49
428+20.53	428+75.00	RT	81
431+75.00	434+75.00	LT	346
431+75.00	434+75.00	RT	691
434+75.00	437+75.00	LT	346
435+00.00	437+75.00	LT	429
434+75.00	435+00.00	RT	57
435+00.00	437+75.00	RT	389
437+75.00	438+40.00	LT	51
437+75.00	438+40.00	RT	46
TOTAL			9,047

SCHEDULE OF RUBRAIL

FROM STATION	TO STATION	OFFSET	(FT)
US ROUTE 30			
421+20.00	423+13.75	LT	194
423+13.75	423+63.57	LT	50
TOTAL			244

SCHEDULE OF TEMPORARY PAVEMENT

FROM STATION	TO STATION	OFFSET	STAGE	TEMPORARY PAVEMENT (SQ YD) Z0062456
US ROUTE 30				
308+50.00	313+25.22	RT	PRE	538
312+67.69	358+95.00	RT	PRE	8,500
207+87.00	373+75.00	RT	PRE	2,938
374+41.00	419+89.41	RT	PRE	6,774
420+47.78	427+40.78	RT	PRE	499
434+99.82	442+75.00	RT/LT	PRE	1,925
DOUGLAS RD.				
206+51.64	210+04.05	RT/LT	PRE	225
211+01.00	213+78.67	RT	PRE	362
US ROUTE 30				
352+20.09	358+53.01	LT	1	363
363+92.56	373+45.22	RT/LT	1	968
372+25.79	373+45.30	RT/LT	1	238
415+86.65	419+79.31	LT	1	414
415+86.63	419+63.15	LT	1	223
421+21.81	424+63.36	LT	1	465
421+15.06	424+63.36	LT	1	220
427+07.03	433+81.10	RT/LT	1	1,079
435+40.23	438+39.98	LT	1	329
US ROUTE 30				
411+18.48	418+47.51	RT/LT	2	595
421+40.72	428+69.97	RT/LT	2	693
TOTAL				27,348

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	11 WRS-3	KENDALL	527	65
CONTRACT NO. 60132				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

FILE NAME = S:\JOL\6300--6399\6346-023\Micro\CAAD Sheets\0160132-sht-schedule.dgn



USER NAME = amanda.j	DESIGNED -	REVISED -
PLOT SCALE = 48.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 8/6/2012	CHECKED -	REVISED -
	DATE -	REVISED -