

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	ALIGNMENT PLAN
5	<i>EXIST./PROP. DRAINAGE, EROSION & SEDIMENT CONTROL</i>
6	<i>PROFILE AND DRAINAGE SECTION</i>
7	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10)
8	ARTERIAL ROAD INFORMATION SIGN (TC-22)

STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001 - 06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS.
280001 - 06	TEMPORARY EROSION CONTROL SYSTEMS.
542301 - 03	PRECAST REINFORCED CONCRETE FLARED END SECTION.
602401 - 03	MANHOLE, TYPE A.
604001 - 03	FRAME AND LIDS TYPE 1.
701101 - 02	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE.
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS.
701606 - 08	URBAN LANE CLOSURE, MULTILANE 2W WITH MOUNTABLE MEDIAN.
701801 - 05	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE.
701901 - 02	TRAFFIC CONTROL DEVICES.

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF BLOOMINGDALE.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

THE RESIDENT ENGINEER SHALL CONTACT DON CHIORUGI, AREA TRAFFIC FIELD ENGINEER, AT 847-715-8416 AT LEAST 2 WEEKS PRIOR TO PLACING PERMANENT PAVEMENT MARKINGS.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE (or CONSTRUCTION or BRIDGE INSPECTORS).

EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

Rev.

FILE NAME *	USER NAME = hmondanah	DESIGNED -	REVISED -	STATE OF ILLINOIS	U.S. 20 - LAKE STREET EAST OF ROSELLE ROAD /BLOOMINGDALE ROAD INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	2011-shc-plen.dgn	DRAWN -	REVISED -			021	2011-069-T	DUPAGE	8	2	
	PLOT SCALE = 50.0000' / 1" =	CHECKED -	REVISED -			CONTRACT NO. 60P88					
	PLOT DATE = 7/6/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					