100% STATE

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES 0044 | CONSTRUCTION TYPE CODE URBAN 0044 | | | | |
|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | | | | | | |
| 20800150 | TRENCH BACKFILL | CU YD | 66 | 66 | | | | |
| 20101000 | TEMPORARY FENCE | FOOT | 43 | 43 | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 204 | 204 | | | | |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 1 | 1 | | | | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.04 | 0.04 | | | | |
| 20101200 | TREE ROOT PRUNING | EACH | 3 | 3 | | | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 4 | 4 | | | | |
| | | | | | | | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 4 | 4 | | | | |
| | | | | | | | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 4 | 4 | | | | |
| | | | | | | | | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 4 | 4 | | | | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 405 | 405 | | | | |
| ~~28000500~~ | ~~INLET AND PIPE PROTECTION~~ | ~~EACH~~ | ~~4~~ | ~~4~~ | | | | |
| 28000510 | INLET FILTERS | EACH | 4 | 4 | | | | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 15 | 15 | | | | |
| | | | | | | | | |
| 28200200 | FILTER FABRIC | SQ YD | 15 | 15 | | | | |
| | | | | | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 310 | 310 | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 41 | 41 | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 310 | 310 | | | | |
| | | | | | | | | |
| 50102400 | CONCRETE REMOVAL | CU YD | 1.2 | 1.2 | | | | |
| | | | | | | | | |
| 54213675 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" | EACH | 1 | 1 | | | | |
| | | | | | | | | |
| 54247150 | GRATING FOR CONCRETE FLARED END SECTION 30" | EACH | 1 | 1 | | | | |
| | | | | | | | | |
| 550A0430 | STORM SEWERS, CLASS A, TYPE 2 30" | FOOT | 226 | 226 | | | | |

100% STATE

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE URBAN 0044 | | | | |
|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | | | | | | |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 15 | 15 | | | | |
| | | | | | | | | |
| 60221100 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | | | | |
| | | | | | | | | |
| 60300350 | MANHOLE FRAMES TO BE ADJUSTED | EACH | 1 | 1 | | | | |
| | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | |
| | | | | | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | |
| | | | | | | | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | | | |
| | | | | | | | | |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 51.4 | 51.4 | | | | |

Rev.

| FILE NAME = | USER NAME = hamdanah | DESIGNED - | REVISED - |
|---|---|---|---|
| c:\pw_work\pwildot\hamdanah\d0273975\D162611\sht_plan.dgn | | DRAWN - | REVISED - |
| | PLOT SCALE = 100.0000 ' / in. | CHECKED - | REVISED - |
| | PLOT DATE = 7/9/2012 | DATE - | REVISED - |

STATE OF ILLINOIS

U.S. 20 – LAKE STREET
EAST OF ROSELLE ROAD /BLOOMINGDALE ROAD
SUMMARY OF QUANTITIES

SHEET NO. OF SHEETS STA. TO STA.

| F.A.P RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 021 | 2011-069-T | DuPAGE | 8 | 3 |
| | | CONTRACT NO. 60P88 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |

D162611-sht-plan.dgn 7/9/2012 1:08:37 PM User=hamdanah