

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 FED. 90% STATE 10%					
44004000	PAVED DITCH REMOVAL	FOOT	551	551					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	64	64					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	59	59					
44300200	<i>STRIP REFLECTIVE CRACK CONTROL TREATMENT</i>	<i>FOOT</i>	<i>1130</i>	<i>1130</i>					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	180	180					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	500	500					
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4					
50105220	PIPE CULVERT REMOVAL	FOOT	116	116					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4					
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4	4					
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	124	124					
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2					
60107600	PIPE UNDERDRAINS 4"	FOOT	1060	1060					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
* SPECIALTY	ITEM								

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 FED. 90% STATE 10%					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	549	549					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	229	229					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6481	6481					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	530	530					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2735	2735					
72000100	SIGN PANEL - TYPE 1	SO FT	61	61					
72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	56	56					
72900100	METAL POST - TYPE A	FOOT	29	29					
72900200	METAL POST - TYPE B	FOOT	74.5	74.5					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	229	229					
* SPECIALTY	ITEM								