

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	100% LOCAL
				ROADWAY	SAFETY	LANDSCAPING	
				0005	0021	0031	0001
				URBAN	URBAN	URBAN	URBAN
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6,360	4,930			1,430
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2,350	2,350			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	307	251			56
44000600	SIDEWALK REMOVAL	SQ FT	6,658	5,833			825
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	21			21	
44201761	CLASS D PATCHES, TYPE 1, 10 INCH	SQ YD	3			3	
44201765	CLASS D PATCHES, TYPE 2, 10 INCH	SQ YD	13			13	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	200	200			
* 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1	1			
60200205	CATCH BASINS, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE 8-6.12	FOOT	614	278			336
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4			2
67100100	MOBILIZATION	L SUM	1	0.9			0.1
* 66900200	NON-SPECIAL WASTE	CU YD	130	130			

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\pripIn-ABC-soq-02.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 8/8/2012	DATE - 8/8/2012	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 2 OF 9 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2865	10-85159-00-TL	COOK	62	5
CONTRACT NO. 63715			ILLINOIS FED. AID PROJECT	