

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	100% LOCAL
				ROADWAY	SAFETY	LANDSCAPING	
				0005 URBAN	0021 URBAN	0031 URBAN	0001 URBAN
* X0324994	ORNAMENTAL PLANTER	L SUM	1			1	
* X0325541	REMOVE EXISTING LIGHTING SYSTEM	L SUM	1		1		
X0326144	TACTILE/DETECTABLE WARNING SURFACE	SQ FT	108		86		22
* X0326326	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO.6 AND 1-1/C NO.8 GROUND	FOOT	565		565		
* X0326805	FOUNDATION REMOVAL	SQ FT	364		364		
* X0539800	TREE GRATES	EACH	2			2	
* X0935000	MAST ARM, STEEL MONOTUBE, 30 FT.	EACH	2		2		
X3112900	SUBBASE GRANULAR MATERIAL (SPECIAL)	CU YD	1,090	1,030			60
X4200408	PORTLAND CEMENT CONCRETE PAVEMENT 8", SPECIAL	SQ YD	77				77
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.9			0.1
* X8050095	SERVICE INSTALLATION, (SPECIAL)	EACH	1		1		
* X8210456	LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 400 WATT, 240 VOLT, ARTERIAL, SEMI-CUTOFF	EACH	4		4		
* X8570015	CONTROLLERS (SPECIAL)	EACH	1		1		
* X8780105	CONCRETE FOUNDATION (SPECIAL)	EACH	1		1		

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\proj\in\ABC-sq-05.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 8/8/2012	DATE - 8/8/2012	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NTS	SHEET NO. 5 OF 9 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2865	10-B5159-00-TL	COOK	62	8
CONTRACT NO. 63715				
ILLINOIS FED. AID PROJECT				