

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	100% LOCAL
				ROADWAY	SAFETY	LANDSCAPING	
				0005	0021	0031	0001
				URBAN	URBAN	URBAN	URBAN
* XX008713	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 19/C	FOOT	679		679		
* XX008714	ELECTRICAL CABLE IN CONDUIT, SIGNAL NO.4 2/C	FOOT	117		117		
* XX008715	EMBEDDED CONCRETE POLE, WITH LOYOLA LED LUMINARE	EACH	4		4		
X4200531	HIGH EARLY STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	354				354
* XX008716	LUMINAIRE, STREET LIGHT, HIGH PRESSURE SODIUM VAPOR, 310 WATT, 240 VOLT, ARTERIAL, CRIME-FIGHTER MODEL	EACH	2		2		
* XX008717	MAST ARM, STEEL, 15 FOOT	EACH	6		6		
* XX008718	MAST ARM, STEEL MONOTUBE, 16 FOOT	EACH	1		1		
* XX008719	POLE, STEEL, ANCHOR BASE, 11" DIA., 3-GAUGE, 34'-6"	EACH	2		2		
* XX008720	POLE, STEEL, ANCHOR BASE, 8-1/2"DIA., 3-GAUGE, 32'-6"	EACH	2		2		
XX008721	PERMEABLE CLAY PAVERS	SQ FT	3,710	3,710			
* XX008722	PERFORATED EXTRA STRENGTH VITRIFIED CLAY PIPE, 8"	FOOT	430	430			
* XX008723	EXTRA STRENGTH VITRIFIED CLAY PIPE, 12"	FOOT	8	8			
* XX008724	TRENCH AND BACKFILL WITH SCREENINGS	FOOT	560		560		
* XX008725	CONTROLLER, STREET LIGHT, BASE MOUNTED, 1 PHASE, 100 AMP	EACH	1		1		

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\ppln-ABC-ssq-08.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 8/8/2012	DATE - 8/8/2012	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 8 OF 9 SHEETS STA. TO STA.

F.A.J. RTE. 2865	SECTION 10-85159-00-TL	COUNTY COOK	TOTAL SHEETS 62	SHEET NO. 11
CONTRACT NO. 63715			ILLINOIS FED. AID PROJECT	