

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				ROADWAY 0005 RURAL
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.9	5.9
40600300	AGGREGATE (PRIME COAT)	TON	30.9	30.9
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	44	44
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,732	1,732
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	15,465	15,465
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	350	350
44201381	CLASS C PATCHES, TYPE III, 12 INCH	SQ YD	250	250
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	75	75
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	710	710

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				ROADWAY 0005 RURAL
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	15,957	15,957
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	119	119
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	15,957	15,957
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	499	499
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	78	78
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	154	154
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	154	154

\* SPECIALTY ITEM