SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	CONSTRUCTION CODE ROADWAY 0001	BRIDGE 0008	RETAINING WALL 0040	SIGNING 0021	ITS 0021	
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	67,030	67,030					
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	55,819	55,819					
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	157	157					
42000526	PORTLAND CEMENT CONCRETE PAVEMENT 11 1/4" (JOINTED)	SQ YD	4,625	4,625					
42001300	PROTECTIVE COAT	SQ YD	69,358	69,358					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,872	1,872					
42100325	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11 1/4"	SQ YD	45,488	45,488					
42100615	PAVEMENT REINFORCEMENT	SQ YD	45,488	45,488					
42101436	LUG SYSTEM COMPLETE 36'	EACH	1	1					
42101447	LUG SYSTEM COMPLETE 47'	EACH	3	3					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	768	768					
48300605	PORTLAND CEMENT CONCRETE SHOULDERS 11 1/4"	SQ YD	11,400	11,400					
50105220	PIPE CULVERT REMOVAL	FOOT	70	70					
50300225	CONCRETE STRUCTURES	CU YD	30.2		30.2				

• DENOTES SPECIALTY ITEMS Δ 0042

..\DBCONN-03-BORDER.DGN ..\DBCONN-03-SDO.DGN ..\DBCONN-99-MOTIF.DGN ..\DBCONN-09-LEGEND.DGN
6-27-2012 11:19:09 DONOHUJO \\fs-0844\VHAL1\D-11\MS_87\2262\28868-000\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 08\DBCONN-08-SHT-SUMMARY2.DGN

FILE NAME = $FILE1$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - JB	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT DATE = $DATE$	DATE - 06/29/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

SUMMARY OF QUANTITIES 2

SCALE: N.T.S. | SHEET NO. 2 OF 10 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-1R	ST. CLAIR	294	5
		CONTRACT NO. 76C43		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		