

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				ROADWAY	BRIDGE	RETAINING WALL	SIGNING	ITS
				0001	0008	0040	0021	0021
50300255	CONCRETE SUPERSTRUCTURE	CU YD	588.1		172.6	415.5		
50300260	BRIDGE DECK GROOVING	SQ YD	295		295			
50300300	PROTECTIVE COAT	SQ YD	1,375		401	974		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	114,140		40,730	73,410		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1				
54215547	METAL END SECTIONS 12"	EACH	5	5				
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	486	486				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	3,063	3,063				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,000	1,000				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,551	1,551				
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	128	128				

• DENOTES SPECIALTY ITEMS Δ 0042

\\03-0044\44\VAL\1.0\TRANS\87\2282\28866-98\1\CIVIL\CAD\50 ALL CONTRACTS\CONNSHEETS CONTRACT 08\08\08\08-88-SHT-SUMMARY\3.DGN
 \\03-0044\44\VAL\1.0\TRANS\87\2282\28866-98\1\CIVIL\CAD\50 ALL CONTRACTS\CONNSHEETS CONTRACT 08\08\08\08-88-SHT-SUMMARY\3.DGN
 \\03-0044\44\VAL\1.0\TRANS\87\2282\28866-98\1\CIVIL\CAD\50 ALL CONTRACTS\CONNSHEETS CONTRACT 08\08\08\08-88-SHT-SUMMARY\3.DGN

FILE NAME *	USER NAME * USER*	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION 1-70 CONNECTION	SUMMARY OF QUANTITIES 3			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILEL		DRAWN - JB	REVISED -		998	82-1R	ST. CLAIR	294	6				
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = *SCALE*	CHECKED - ACL	REVISED -		SCALE: N.T.S.			SHEET NO. 3 OF 10 SHEETS		STA.	TO STA.	CONTRACT NO. 76C43	
	PLOT DATE = *DATE*	DATE - 06/29/12	REVISED -		ILLINOIS FED. AID PROJECT								