CONCRETE SHOULDER CURB — TOTAL 883 FOOT

LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
PR I-70	140+97.31	42.9 RT	148+00.00	55.5 RT	684
PR I-70	148+00.00	55.5 RT	150+01.01	55.5 RT	199

CHAIN LINK FENCE, 6' — TOTAL 34 FOOT

LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
PR I-70 BEHIND ABUTMENT MSE WALL BEHIND CONCRETE GUTTER, TYPE B	140+68.53	42.9 RT	140+61.23	69.9 RT	34

WOVEN WIRE FENCE, 4' — TOTAL 544 FOOT

LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
PR I-70	179+37.28	234.0 LT	179+37.28	214.0 LT	20
PR I-70	179+37.28	202.0 LT	182+84.69	202.0 LT	504
PR I-70	182+84.70	214.0 LT	182+84.71	234.0 LT	20

WOVEN WIRE GATES, 4' X 12' SINGLE — TOTAL 2 EACH

LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
PR I-70	179+37.28	202.0 LT	179+37.28	214.0 LT	1
PR I-70	182+84.69	202.0 LT	182+84.70	214.0 LT	1

FURNISHING AND ERECTING RIGHT OF WAY MARKERS — TOTAL 2 EACH

LOCATION	STA	OFFSET	SUBTOTALS
PR I-70	147+08.72	178.54 LT	1
PR I-70	148+52.09	378.35 RT	1

GUARDRAIL MARKERS, TYPE A — TOTAL 44 EACH

LOCATION	FROM STA.	TO STA.	LT/ RT	LENGTH (FT)	SPACING	SUBTOTALS
PR I-70	140+90.29	150+01.01	RT	911	50	18
PR I-70	147+35.00	151+48.41	LT	413	50	8
PR I-70	156+37.51	158+00.00	RT	162	50	3
PR I-70	186+00.19	192+14.00	RT	614	50	12
PR I-70	190+49.34	192+14.00	LT	165	50	3

BARRIER WALL MARKERS, TYPE C — TOTAL 249 EACH

LOCATION	STA.	STA.	LENGTH (FT)	SPACING (FT)	COLOR	OFFSET	SUBTOTALS
PR I-70	127+81.00	140+64.00	1,283	40	AMBER	CL EB	33
PR I-70	127+81.00	140+64.00	1,283	40	AMBER	CL WB	33
PR I-70	127+81.00	140+64.00	1,283	40	CRYSTAL	RT	33
PR I-70	127+81.00	140+64.00	1,283	40	CRYSTAL	LT	33
PR I-70	140+64.00	148+85.08	821	40	AMBER	CL	21
PR I-70	140+64.00	147+35.00	671	40	CRYSTAL	LT	17
PR I-70	148+85.08	152+85.00	400	80	AMBER	CL	5
PR I-70	152+85.00	155+85.00	300	80	AMBER	CL	4
PR I-70	155+85.08	162+00.00	615	80	AMBER	CL	8
PR I-70	162+00.00	176+00.00	1,400	80	AMBER	CL	18
PR I-70	176+00.00	183+32.89	733	80	AMBER	CL	10
PR I-70	183+32.89	189+28.42	596	40	AMBER	CL	15
PR I-70	189+28.42	190+00.00	72	80	AMBER	CL	1
PR I-70	190+00.00	191+99.00	199	80	AMBER	CL	3
PR I-70	166+83.32	178+25.00	1,142	80	CRYSTAL	RT	15

INCLUDES BARRIER MARKERS ALONG I-70. BARRIER MARKERS ALONG RAMPS AND RELOCATED IL 3 TO BE INCLUDED IN CONTRACT 76E06

AGGREGATE SURFACE COURSE, TYPE B 8" — TOTAL 370 SQ YD

	FROM		TO			
LOCATION	STA.	OFF.	STA.	OFF.	WIDTH FT	SUBTOTALS
PR I-70	182+84.69	202.0 LT	185+00.03	210.0 LT	16	370

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 (VARIABLE WIDTH GUTTER FLAG) — TOTAL 75 FOOT

	FROM		TO		
LOCATION	STA	OFF	STA	OFF	SUBTOTALS
PR I-70	171+20.48	47.08 RT	171+70.52	46.08 RT	50
PR I-70	179+67.05	45.50 RT	179+92.09	46.05 RT	25

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 — TOTAL 1,760 FOOT

	FROM		TO		
LOCATION	STA	OFF	STA	OFF	SUBTOTALS
PR I-70	163+81.76	61.86 RT	171+20.48	47.08 RT	739
PR I-70	171+70.52	46.08 RT	176+00.00	45.77 RT	429
PR I-70	176+00.00	45.77 RT	179+67.05	45.50 RT	367
PR I-70	179+92.09	46.5 RT	182+17.05	55.50 RT	225

REMOVE TEMPORARY CONCRETE BARRIER — TOTAL 788 FOOT

	FROM		TO		
LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
PR I-70	179+37.28	234.0 LT	182+84.64	234.0 LT	788