CONTRACT 76C43
PAVING LIMITS
END AT STA 191+99.00

PAVEMENT MARKING & SIGNING ONLY
PAVING BY OTHERS
CONTRACT 76C50

PROPOSED I-70 PGL

451.29

+2.10%

FINISHED GRADE AT
I-70 PGL CONSTRUCTED
BY 76C41

APPROACH SLAB
BY 76C50

PAVING LIMITS

1.91'

1ST STREET BRIDGE
(BY OTHERS)

2.11'

1.42'

EXISTING GROUND AT ℄ I-70

MATCH LINE STA. 190+00
SEE SHEET 45

℄ 1ST. STREET

EXISTING GROUND AT ℄ I-70	421.42	421.46	421.06	421.07	421.07	420.37	419.41	420.02	419.78	419.40	419.20	418.83	418.67
PR. PGL ELEV.	437.95	439.00	440.05	441.10	442.15	443.20	444.25	445.30	446.35	447.40	448.45	449.50	450.55

190+00 191+00 192+00 193+00 194+00 195+00 196+00

470 465 460 455 450 445 440 435 430 425 420 415 410 405 400 395 390 385

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / GRADES CHECKED / STRUCTURE NOTES CHKD / CADD FILE NAME / NOTE BOOK / NO. / BY / DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / STRUCTURE NOTES CHKD / NOTE BOOK / NO. / BY / DATE

6-27-2012 9:49:08 AM V:\ES-2012_JAN\ROAD_D-TRANS_D\22X2C-28658-WR\CIVIL\CADD\99 ALL CONTRACTS\CONN SHEETS CONTRACT 06\DRCONN-08-SHT-PROF-190800.DGN

FILE NAME = $FILE1$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - JB	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
	PLOT DATE = $DATE$	DATE - 06/29/12	REVISED -

TENG — TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

PROPOSED I-70
ROADWAY PROFILE
STA. 190+00 TO TRI-LEVEL

SCALE: HORIZ. 1"=50' VERT. 1"=5' STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-1R	ST. CLAIR	294	46
		CONTRACT NO. 76C43		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		