DIRECTION	STATION	OFFSET	SHEET NO.	SIGN I.D.	DESCRIPTION	SIGN STRUCTURE #	PROPOSED SIGN SIZE WIDTH (FT)	HEIGHT (FT)	AREA SQ FT	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	SIGN PANEL TYPE 3 SQ FT	SIGN PANEL TYPE 3 (SPECIAL) SQ FT	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN (FT)	SIGN SUPPORT SPECIAL (EA)
EB I-70	69+44	RT	156	1	EXIT 2, IL 3, 1 3/4 MILES	N/A - MODOT	17.5	12.5	218.75				218.75			
EB I-70	130+03	RT	157	2	EXIT 2, IL 3, 1/2 MILE	8C082I070R001.1	17.5	12.5	218.75				218.75			
EB I-70	133+98	RT	157	D10-5-01.2E	EAST I-70 MILE 1.2	N/A	1.5	5	7.5	7.5						1
WB I-70	133+98	LT	157	D10-5-01.2W	WEST I-70 MILE 1.2	N/A	1.5	5	7.5	7.5						1
EB I-70	144+54	RT	158	D10-5-01.4E	EAST I-70 MILE 1.4	N/A	1.5	5	7.5	7.5						1
WB I-70	144+54	LT	158	D10-5-01.4W	WEST I-70 MILE 1.4	N/A	1.5	5	7.5	7.5					18	
EB I-70	147+60	RT	158	3	MOVE OVER - SLOW DOWN	8S082I070R001.5	15	8	120				120			
EB I-70	147+60	RT	158	4	WELCOME TO ILLINOIS	8S082I070R001.5	14	7	98				98			
WB I-70	147+60	LT	158	5	EXIT 249, TUCKER BLVD, I-70 WEST	8S082I070R001.5	27.5	18.5	508.75				508.75			
WB I-70	147+60	LT	158	R2-1	SPEED LIMIT 55	N/A	4	5	20		20					
EB I-70	153+00	RT	159	R16-5	LIGHTS ON WHEN USING WIPERS	N/A	4	5	20		20			18		
EB I-70	155+10	RT	159	D10-5-01.6E	EAST I-70 MILE 1.6	N/A	1.5	5	7.5	7.5					18	
WB I-70	155+10	LT	159	D10-5-01.6W	WEST I-70 MILE 1.6	N/A	1.5	5	7.5	7.5					18	
WB I-70	157+00	LT	159	W4-1	MERGE AHEAD	N/A	4	4	16		16			17		
EB I-70	158+00	RT	159	6	EXIT 2 IL 3, RIGHT	8C082I070R001.7	21	10.5	220.5				220.5			
EB I-70	161+50	RT	159	W13-3	RAMP 30 M.P.H.	N/A	3	4	12		12			17		
EB I-70	164+85	RT	160	E5-1A-2	EXIT 2, RIGHT	N/A	6.5	5	32.5			32.5		• 36		
EB I-70	165+66	RT	160	D10-5-01.8E	EAST I-70 MILE 1.8	N/A	1.5	5	7.5	7.5					18	
WB I-70	165+66	LT	160	D10-5-01.8W	WEST I-70 MILE 1.8	N/A	1.5	5	7.5	7.5					18	
WB I-70	166+31	LT	160	E5-1A-2	EXIT 2, RIGHT	N/A	6.5	5	32.5			32.5		• 36		
WB I-70	168+00	LT	160	W13-3	RAMP 30 M.P.H.	N/A	3	4	12		12			17		
EB I-70	172+40	RT	160	7	EXIT 3, I-64 EAST LOUISVILLE 1/2 MILE	8B082I070R001.9	13.5	12.5	168.75				168.75			
WB I-70	173+02	LT	160	8	EXIT 2, IL 3 EXIT ONLY RIGHT	8B082I070L001.9	17.5	13	227.5				227.5			
EB I-70	176+22	RT	161	D10-5-02.0E	EAST I-70 MILE 2.0	N/A	1.5	5	7.5	7.5					18	
WB I-70	176+22	LT	161	D10-5-02.0W	WEST I-70 MILE 2.0	N/A	1.5	5	7.5	7.5					18	
EB I-70	181+40	RT	161	W4-3	MERGE AHEAD	N/A	4	4	16		16			18		
EB I-70	186+78	RT	161	D10-5-02.2E	EAST I-70 MILE 2.2	N/A	1.5	5	7.5	7.5					18	
WB I-70	186+78	LT	161	D10-5-02.2W	WEST I-70 MILE 2.2	N/A	1.5	5	7.5	7.5					18	
EB I-70	188+00	RT	161	9	EAST I-70 TO EAST 40 TO NORTH I-55	8S082I070R002.2	18.5	16.5	305.25				305.25			
EB I-70	188+00	RT	161	10	EXIT 3, I-64 EAST LOUISVILLE 1/4 MILE, EXIT ONLY	8S082I070R002.2	14.5	15.5	224.75				224.75			
EB I-70	188+00	RT	161	R2-1	SPEED LIMIT 55	N/A	4	5	20		20					
WB I-70	189+00	LT	161	R2-1	SPEED LIMIT 55	N/A	4	5	20		20					
WB I-70	195+00	LT	162	11	EXIT 2, IL 3, 1/2 MILE EXIT ONLY	8S082I070L002.4	17.5	15.5	271.25				271.25			
55S70W	72+90	RT	163	12	EXIT 2, IL 3, 3/4 MILE EXIT ONLY	8C082I070L002.7	17.5	15.5	271.25				271.25			
64W70W	71+30.79	RT	163	13	EXIT 2, IL 3, 3/4 MILE	8C082I070R002.7	17.5	12.5	218.75				218.75			
									TOTAL	90.0	136.0	65.0	3,072.25	159.0	162.0	3

• NOTE: TWO SIGN POSTS ARE INCLUDED IN THE TOTAL LENGTH

SIGN REMOVALS

DIRECTION	STATION	OFFSET	SHEET NO.	DESCRIPTION	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH
BAUGH AVE.	403+00	RT	164	TO / NORTH / IL 3 / UP ARROW	1

\\DBCONN-99-NOTIFI.DGN,\\DBCONN 08-BRDEFRI.DGN,\\DBCONN-08-NOTIFI.DGN,\\DBCONN-11-NOTIFI.DGN,\\DBCONN-08-LEGEND.DGN
6-27-2012 4:33:57 BONDALJD \\FS 0844\AM\VAULT\D-TRANS.07\2202\20868-001\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 08\DBCONN-08-SHT-SIGNS1-5.DGN