SIGN DETAIL
1:100

1:100

(12)

SIGN I.D.

STR. NUMBER	8C082I070L002.7
WIDTH x HGHT.	17'-6" x 15'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: ZZ Retro Reflective
	COLOR: Color 24 /Color 9
LEGEND/BORDER	TYPE: ZZ Retro Reflective
	COLOR: Color 100 /Color 218 /Color 100

	SYMBOL	ROT	X	Y	WID	HT
M1-1	100A-2-22-10D	0	85.4	70	39.3	36
	ARDOWN	0	84.4	8.4	29.9	20.5

Panel Style: guide_fwy_overhead_2009_exit.ssi
Dimensions are in inches.tenths

BORDER R=12"

FONT: (1) ClearviewHwy-5-W

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

													LENGTH	SERIES/SIZE
E	X	I	T	2										ClearviewHwy-5-W
136.5	145.1	156.6	161.5	183.7									57.5	10,15
E	a	s	t		S	t		L	o	u	i	s		ClearviewHwy-5-W
17.1	31.7	47.4	61.1	69	85.5	100.6	108.5	126.2	139.9	157.7	174.4	182.6	175.7	16/13
3/4	M	I	L	E										ClearviewHwy-5-W
69.5	105.8	118.9	124.9	134									70.9	15,10
E	X	I	T											ClearviewHwy-5-W
33.7	44	57.7	63.7										38.6	12
O	N	L	Y											ClearviewHwy-5-W
131	146.4	161.1	170.4										50	12

Kaskaskia Engineering Group, LLC

USER NAME = $USER$	DESIGNED - SMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
FILE NAME = $FILEL$	DRAWN - RJO	REVISED -	
PLOT SCALE = $SCALE$	CHECKED - LDC	REVISED -	I-70 CONNECTION
PLOT DATE = $DATE$	DATE - 06/29/12	REVISED -	

SIGN PANEL DETAILS

SCALE: | SHEET NO. 12 OF 14 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-1R	ST. CLAIR	294	177
		CONTRACT NO. 76C43		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		