

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0014 100% STATE		
35501319	HOT-MIX ASPHALT BASE COURSE, 8 3/4"	SQ YD	163	163		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	74.4	74.4		
44004250	PAVED SHOULDER REMOVAL	SQ YD	163	163		
50102400	CONCRETE REMOVAL	CU YD	13.6	13.6		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	13.2	13.2		
50300300	PROTECTIVE COAT	SQ YD	32	32		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1760	1760		
50800515	BAR SPLICERS	EACH	24	24		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	92	92		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	892	892		
67100100	MOBILIZATION	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION STANDARD 70132.6	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6		

FILE NAME *	USER NAME * ohallandeske	DESIGNED -	REVISED -
cr:\pwork\prido\ohallandeske\d0292381	0876F53-shr-SQ.dgn	DRAWN -	REVISED -
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE * 7/12/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE	SHEET 1	OF 3	SHEETS	STA.	TO STA.	F.A.P RTE. 861	SECTION 110-BR	COUNTY RANDOLPH	TOTAL SHEETS 20	SHEET NO. 3
						CONTRACT NO. 76F53				
ILLINOIS FED. AID PROJECT										