

PAVEMENT MARKING SCHEDULE												
				THERMOPLASTIC PAVEMENT MARKING			TEMPORARY PAVEMENT MARKING			WORK ZONE	RAISED	
				EDGE LINE	CENTERLINE	CENTERLINE	EDGE LINE	CENTERLINE	CENTERLINE	STOP BAR	PAVEMENT	REFLECTIVE
				SOLID	SKIP-DASH	SOLID	SOLID	SKIP-DASH	SOLID	SOLID	MARKING	PAVEMENT
				4" WHITE	4" YELLOW	4" YELLOW	4" WHITE	4" YELLOW	4" YELLOW	24" WHITE	REMOVAL	MARKER (BRIDGE)
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH
STA.	821+50.40	TO	STA. 827+13.75	1126.7	140.8		1126.70	140.84			422.5	
STA.	822+41.00	TO	STA. 827+13.75			472.8			472.75		157.6	
STA.	823+82.00	TO	STA. 825+75.00									3
			STA. 820+62						12	24		
			STA. 828+47						13	26		
SUB-TOTAL				1126.7	140.8	472.8	1126.7	140.8	472.8	25	630.1	3
GRAND TOTAL				1,740			1,740			25	630	3

PAVING SCHEDULE					
			HOT-MIX	PAVED	
			ASPHALT	SHOULDER	
STATION			BASE COURSE 8 3/4"	REMOVAL	
STAGE 1			SQ YD	SQ YD	
WB	822+70.00	TO 823+67.00	43.11	43.11	
EB	825+90.00	TO 827+13.75	41.25	41.25	
STAGE 2					
WB	822+82.50	TO 823+67.00	37.56	37.56	
EB	825+90.00	TO 827+13.75	41.25	41.25	
TOTAL			163	163	

STAGING SCHEDULE							
	TEMPORARY	RELOCATE	IMPACT ATTENUATORS	IMPACT ATTENUATORS	IMPACT ATTENUATORS	IMPACT ATTENUATORS	
	CONCRETE	CONCRETE	TEMPORARY	RELOCATE	TEMPORARY	RELOCATE	TEMPORARY
	BARRIER	BARRIER	(NON-REDIRECTIVE, NARROW),	(NON-REDIRECTIVE, NARROW),	(NON-REDIRECTIVE),	(NON-REDIRECTIVE),	RUMBLE
STAGE	TEST LEVEL 3	TEST LEVEL 3	TEST LEVEL 3	TEST LEVEL 3	TEST LEVEL 3	TEST LEVEL 3	STRIP
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
STAGE I	437.5		1		1		
STAGE II		412.5		1		1	
STAGE I & II							6
							1
TOTAL	437.5	412.5	1	1	1	1	6