

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		100% STATE URBAN 0014		CODE NO	ITEM	UNIT		100% STATE URBAN 0014	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	30	30		50300300	PROTECTIVE COAT	SQ YD	207	207	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	98	98		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1260	1260	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	134	134		50800515	BAR SPLICERS	EACH	22	22	
40600990	TEMPORARY RAMP	SQ YD	47	47		52000110	PREFORMED JOINT STRIP SEAL	FOOT	72	72	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	202	202		58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	713	713	
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3		59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	106	106	
40800030	AGGREGATE (PRIME COAT)	TON	2	2		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1	1		67100100	MOBILIZATION	L SUM	1	1	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	346	346		70100320	TRAFFIC CONTROL AND PROTECTION STANDARD 701422	L SUM	1	1	
50102400	CONCRETE REMOVAL	CU YD	10.9	10.9		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
50157300	PROTECTIVE SHIELD	SQ YD	345	345		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
50300225	CONCRETE STRUCTURES	CU YD	0.9	0.9		70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.9	10.9		70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6	
						70300100	SHORT TERM PAVEMENT MARKING	FOOT	982	982	