

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE												
				URBAN ROADWAY		RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDDT LIGHTING		
				J000	Y007	O16-W923	O16-W931	STR NO 016-0142	STR NO 016-1148						Y002-1C	SFTY-3N
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4										4			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1										1			
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	1,017	1,017												
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1												
Z0076600	TRAINEES	HR	1500	1500												
X0325499	AERIAL CABLE, 2 1/2 NO. 4	FOOT	150												150	
X0325491	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., SCH. 80 PVC	FOOT	653												653	
X0325492	CONVENTIONAL STREET LIGHTING UNIT WALL MOUNTED, INSTALL ONLY	EACH	8												8	
X0325494	GALVANIZED STEEL CONDUIT IN TRENCH, 2" DIA., SCH. 40	FOOT	25												25	
B0700110	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	8												8	
X0325500	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, TYPE J	EACH	2											2		
X0324223	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1												1	
X0945500	PAINT EXISTING POLE COMPLETE	EACH	8												8	
X0325495	REMOVE EXISTING STREET LIGHTING UNIT AND SALVAGE	EACH	9												9	
X0324901	REMOVE EXISTING STREET LIGHTING FOUNDATION	EACH	9												9	
X0325496	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	25												25	
X0325493	CABLE IN CONDUIT, <sup>TRIPLEX</sup> 2-1/2 NO. 6 AND 1-1/2 NO. 8 GND.	FOOT	840												840	
X0325501	FABRIC REINFORCED ELASTOMERIC MAT	SO FT	63				63									
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SO FT	15							15						
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SO FT	993					458	535							
XX004210	DUCTILE IRON PIPE STORM SEWERS, 12"	FOOT	143	143												
X0325502	MEDIAN BARRIER GATE SYSTEM	EACH	1	1												
X0325503	REMOVAL OF EXISTING TEMPORARY SOIL RETENTION SYSTEM	FOOT	926	926												
46900200	NON-SPECIAL WASTE DISPOSAL	CU YD	4,500	4,500												
46900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1												
46900530	SOIL DISPOSAL ANALYSIS	EACH	2	2												

\* DENOTES SPECIALTY ITEMS

© 2006

CTE | AECOM

- ▲ Rev. 9-13-06
- ▲ Rev. 9-11-06
- ▲ Rev. 8-21-06

S00-7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH  
 DATE: June 9, 2006 CHECKED BY: RMG

S-33-13 AM 6/6/2006