

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE										
				URBAN		URBAN ROADWAY	RETAINING WALL 69TH STREET SOUTHWEST	BRIDGE		SIGNING	LIGHTING	SURVEILLANCE	SAFETY	CDDT LIGHTING
				J000	Y007			STR NO 016-0142	STR NO 016-1148					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1										
Z0076600	TRAINEES	HOUR	1,500	1,500										
X0325491	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., SCH. 80 PVC	FOOT	351										351	
X0325492	CONVENTIONAL STREET LIGHTING UNIT WALL MOUNTED, INSTALL ONLY	EACH	5										5	
X0325494	GALVANIZED STEEL CONDUIT IN TRENCH, 2" DIA., SCH. 40	FOOT	70										70	
B0700110	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	5										5	
X0324223	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1										1	
X0945500	PAINT EXISTING POLE COMPLETE	EACH	5										5	
X0325495	REMOVE EXISTING STREET LIGHTING UNIT AND SALVAGE	EACH	5										5	
X0325496	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	70										70	
X0325493	CABLE IN CONDUIT, ^{TRIPLEX,} 2-1/C NO. 6 AND 1-1/C NO. 8 GND.	FOOT	501										501	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	1,618			715	903							
X0325497	STRUCTURAL REPAIR OF CONCRETE (SPECIAL)	SQ FT	1,196			1,196								
XX004210	DUCTILE IRON PIPE STORM SEWERS, 12"	FOOT	134	134										
W900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,000	2,000										
W900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1										
W900530	SOIL DISPOSAL ANALYSIS	EACH	2	2										

© 1080

• DENOTES SPECIALTY ITEMS

CTE | AECOM

3 Rev. 9-13-06
 2 Rev. 9-11-06
 1 Rev. 8-21-06

S00-6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: June 9, 2006

DRAWN BY: NJH
 CHECKED BY: RMG

8/16/2006 9:58:57 AM