F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	247	10
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A63 * (1919.15, 2021-922 PT1 & PT2) R-2

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	QUANTITY (URBAN)	90% FEDERAL / 10% STATE: URBAN ROADWAY J000	RETAINING WALL: 69TH STREET SOUTHWEST Y007	BRIDGE: STR NO 016-0142 SFTY-2A	BRIDGE: STR NO 016-1148 SFTY-2A	SIGNING Y002-1C	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	SAFETY SFTY-3N	CDOT LIGHTING Y030-1E
*	73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	4					4				
*	73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4					4				
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	34,070	34,070								
*	78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	10,022	10,022								
*	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	12,781	12,781								
*	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	2,275	2,275								
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,130	1,130								
*	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	263	263								
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	3	3								
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	131	131								
*	78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	1	1								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	22,846	22,846								
*	80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	1						1			
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	370							370		
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	10						10			
*	81023750	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	185							185		
*	81400200	HEAVY-DUTY HANDHOLE	EACH	3							3		
*	81400205	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	3							3		
*	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	848						245	603		
*	C2011136	SHRUB, SYRINGA X PERSICA (PERSIAN LILAC) 3' HEIGHT, BALLED AND BURLAPPED	EACH	144	144								
*	C2C05818	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 18" WIDTH, CONTAINER	EACH	463	463								
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	234	234								
*	E20220G1	VINE-PARTHENOCISSUS TRICUSPIDATA (BOSTON IVY), 1-GALLON POT	EACH	108	108								
*	K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	4.67	4.67								
	X0320333	ROADWAY CLEANING (SPECIAL)	EACH	19	19								
	X0321720	WATER MAIN REMOVAL	FOOT	287	287								
*	X0321905	STORM SEWERS, TYPE 1, WATERMAIN QUALITY PIPE, 12"	FOOT	161	161								
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	684	684								
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	18	18								
	X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	1.7	1.7								

* DENOTES SPECIALTY ITEMS

CTE | AECOM

S00-4

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

P:\90-94&BVD\INB-ctrs 18 & 19\ST\cntr 19\general\sq00420us.tif 6/6/2006 9:39:56 AM