

EARTHWORK SCHEDULE

STATION TO STATION		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EARTH EXCAVATION (SPECIAL)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE *	EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)	EXCAVATE EXISTING GRANULAR MATERIAL	PLACE EXISTING GRANULAR MATERIAL	EXISTING GRANULAR MATERIAL BALANCE WASTE(+) OR SHORTAGE(-)
		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
3419+00.00	3420+00.00	113	226	0	193	6	+187	0	0	0
3420+00.00	3421+00.00	110	175	0	149	17	+132	0	0	0
3421+00.00	3422+00.00	52	25	0	22	15	+7	0	0	0
3422+00.00	3423+00.00	49	343	0	292	2	+290	0	0	0
3423+00.00	3424+00.00	97	633	0	539	17	+522	17	0	+17
3424+00.00	3425+00.00	88	646	0	550	17	+533	34	0	+34
3425+00.00	3426+00.00	69	707	0	601	4	+597	34	0	+34
3426+00.00	3427+00.00	54	707	0	601	4	+597	34	0	+34
3427+00.00	3428+00.00	25	626	0	533	2	+531	34	0	+34
3428+00.00	3429+00.00	0	552	0	470	28	+442	34	0	+34
3429+00.00	3430+00.00	0	518	0	441	28	+413	34	0	+34
3430+00.00	3431+00.00	0	465	0	396	0	+396	34	0	+34
3431+00.00	3432+00.00	0	463	0	394	0	+394	34	0	+34
3432+00.00	3433+00.00	0	472	0	402	0	+402	34	0	+34
3433+00.00	3434+00.00	0	498	0	424	0	+424	34	0	+34
3434+00.00	3435+00.00	0	526	0	448	0	+448	34	0	+34
3435+00.00	3436+00.00	0	529	0	450	0	+450	34	0	+34
3436+00.00	3437+00.00	0	548	0	466	0	+466	34	0	+34
3437+00.00	3438+00.00	12	572	0	487	0	+487	34	0	+34
3438+00.00	3439+00.00	26	563	0	479	0	+479	34	0	+34
3439+00.00	3440+00.00	32	542	0	461	10	+451	34	0	+34
3440+00.00	3441+00.00	34	552	0	470	1	+469	34	0	+34
3441+00.00	3442+00.00	34	593	0	505	1	+504	35	0	+35
3442+00.00	3443+00.00	38	652	0	555	1	+554	37	0	+37
3443+00.00	3444+00.00	43	627	0	533	1	+532	33	0	+33
3444+00.00	3445+00.00	52	563	0	479	2	+477	28	0	+28
3445+00.00	3446+00.00	63	503	0	428	0	+428	29	0	+29
3446+00.00	3447+00.00	65	421	8	365	91	+274	26	0	+26
3447+00.00	3448+00.00	41	477	10	414	110	+304	23	0	+23
3448+00.00	3449+00.00	10	557	2	476	19	+457	23	0	+23
3449+00.00	3450+00.00	43	483	4	414	65	+349	23	0	+23
3450+00.00	3451+00.00	89	607	4	520	65	+455	23	0	+23
3451+00.00	3452+00.00	93	857	0	729	0	+729	23	0	+23
3452+00.00	3453+00.00	86	879	0	748	0	+748	23	0	+23
3453+00.00	3454+00.00	71	798	0	679	0	+679	23	0	+23
3454+00.00	3455+00.00	60	739	0	629	0	+629	23	0	+23
3455+00.00	3456+00.00	58	983	0	836	0	+836	23	0	+23
3456+00.00	3457+00.00	60	1,268	0	1,078	0	+1,078	23	0	+23
3457+00.00	3458+00.00	54	1,233	0	1,049	0	+1,049	23	0	+23
3458+00.00	3459+00.00	47	1,135	0	965	0	+965	27	0	+27
3459+00.00	3460+00.00	41	1,030	0	876	0	+876	32	0	+32
3460+00.00	3461+00.00	32	937	0	797	0	+797	32	0	+32
3461+00.00	3462+00.00	13	859	0	731	0	+731	32	0	+32
3462+00.00	3463+00.00	0	764	0	650	0	+650	27	0	+27
3463+00.00	3464+00.00	4	602	0	512	0	+512	23	0	+23
3464+00.00	3465+00.00	8	461	0	392	0	+392	23	32	-9
3465+00.00	3466+00.00	12	470	0	400	0	+400	23	102	-79
3466+00.00	3467+00.00	15	509	0	433	0	+433	23	141	-118
3467+00.00	3468+00.00	15	535	0	455	0	+455	23	141	-118
3468+00.00	3469+00.00	15	539	0	459	0	+459	23	141	-118
3469+00.00	3470+00.00	15	516	0	439	0	+439	23	141	-118
3470+00.00	3471+00.00	17	542	0	461	0	+461	23	141	-118
3471+00.00	3472+00.00	25	565	0	481	2	+479	23	141	-118
3472+00.00	3473+00.00	34	568	0	483	4	+479	23	141	-118
3473+00.00	3474+00.00	19	522	0	444	2	+442	23	141	-118
3474+00.00	3475+00.00	0	474	0	403	0	+403	23	141	-118
3475+00.00	3475+50.00	0	245	0	209	0	+209	12	71	-59
TOTAL		2,033	34,401	28	29,295	514	+28,781	1,474	1,474	0

\* THE SHRINKAGE FACTOR USED TO CALCULATE EARTHWORK QUANTITIES IS 15%. FACTOR IS FOR BOTH EARTH EXCAVATION AND EARTH EXCAVATION (SPECIAL) QUANTITIES.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SCHEDULE OF QUANTITIES

SCALE: NONE  
 DATE: June 9, 2006

DRAWN BY: NJH  
 CHECKED BY: RMG



SCH-3

F:\P\060603\IN\B-C\18 & 19\SM\INT. 19\AS\Schedule\SCH\B00324.dwg 6/5/2006 6:04:49 PM