

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
S00-01 OF 8				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% URBAN	CONSTRUCTION TYPE CODE																
				ROADWAY Sta. 573+00.00 to Sta. 789+00.00 I000-2A	US 30 Sta. 587+80.82 X231-2A	EJ&E SB Sta. 608+37.25 X171-5B	EJ&E NB Sta. 608+37.25 X171-5B	MINK Sta. 630+09.46 X020-2A	RENWICK Sta. 631+48.98 SFTY-2A	MS Sta. 710+34.50 X131-2A	LILLY CACHE Sta. 773+45.67 X020-2A	RTE 126 Sta. 781+12.54 SFTY-2A	LIGHTING Sta. 573+00.00 to Sta. 789+00.00 Y030-1E							
20101000	TEMPORARY FENCE	FOOT	470	470																
20200100	EARTH EXCAVATION	CU YD	19,780	19,780																
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9,560	8,985							10	565								
20400800	FURNISHED EXCAVATION	CU YD	12,460	12,460																
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	10								10									
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	925		145	75	40	45			55	565								
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	530	530																
20800150	TRENCH BACKFILL	CU YD	3,897	3,897																
<del>21001000</del>	<del>GEOTECHNICAL FABRIC FOR GROUND STABILIZATION</del>	<del>SQ YD</del>	<del>1586</del>	<del>1586</del>																
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,540	1,540																
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	17,486	17,486																
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	11,480	11,480																
25000210	SEEDING, CLASS 2A	ACRE	9.25	9.25																
25000310	SEEDING, CLASS 4	ACRE	2.00	2.00																
25000314	SEEDING, CLASS 4B	ACRE	0.25	0.25																
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	813	813																
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	813	813																
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	813	813																
25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.50	0.50																
25100115	MULCH, METHOD 2	ACRE	14.25	14.25																
25100630	EROSION CONTROL BLANKET	SQ YD	107,733	107,733																
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,412	1,412																
28000300	TEMPORARY DITCH CHECKS	EACH	20	20																
28000500	INLET AND PIPE PROTECTION	EACH	15	15																
28000510	INLET FILTERS	EACH	107	107																
28100105	STONE RIPRAP, CLASS A3	SQ YD	292	292																
28100107	STONE RIPRAP, CLASS A4	SQ YD	440	25					15		270	130								
28200200	FILTER FABRIC	SQ YD	579	145					15		289	130								
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	8,177	8,177																
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	3,333	3,333																
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41,167	41,167																
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	19.4	19.4																
40600895	CONSTRUCTING TEST STRIP	EACH	3	3																
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1,328	1,328																
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	827	827																

REVISIONS	
NAME	DATE
S. VERTHEIN	08/01/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55  
 US 30 (PLAINFIELD ROAD) TO LILLY CACHE SLOUGH

SUMMARY OF QUANTITIES

SCALE: NONE  
 DATE: 07-21-06

DRAWN BY AR  
 CHECKED BY SV

Rev. 9-15-06  
 Rev. 9-5-06

