

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		SQ0-08 OF 8		

CODE NO.	ITEM	UNIT	URBAN STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
				ROADWAY Sta. 573+00.00 to Sta. 789+00.00 1000-2A	US 30 Sta. 587+80.82 X231-2A	EJ&E SB Sta. 608+37.25 X171- 5B	EJ&E NB Sta. 608+37.25 X171- 5B	MINK Sta. 630+09.46 X020-2A	RENWICK Sta. 631+48.98 SFTY-2A	MS Sta. 710+34.50 X131- 2A	LILLY CACHE Sta. 773+45.67 X020-2A	RTE 126 Sta. 781+12.54 SFTY-2A	LIGHTING Sta. 573+00.00 to Sta. 789+00.00 Y030-1E			
X6050700	REMOVE INLET BOX	EACH	8	8												
X6370905	BARRIER BASE	FOOT	11,700	11,700												
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	11,518	11,518												
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12												
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1												
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	274	274												
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	7	7												
* X8160370	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	410													410
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	61,315	61,315												
Z0002600	BAR SPLICERS	EACH	3,020		1,406	1,192	190				232					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1												
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1												
△ Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4												
△ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	12	12												
△ Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	10	10												
△ Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	10	10												
△ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13	13												
Z0047300	PROTECTIVE SHIELD	SQ YD	1,597		998	470	129									
Z0076600	TRAINEES	HOOR	1,000	1,000												
X0325561	CULVERTS TO BE GROUTED	CU YD	26	26												
X8110145	CONDUIT ATTACHED TO STRUCTURE, 1" DIA. RIGID GALVANIZED STEEL PVC COATED	FOOT	320													320
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	390		20	73	18	10	91				178			
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	5		5											
△ X0325562	BITUMINOUS BASE COURSE SUPERPAVE, N50, 2 1/2"	SQ YD	49,877	49,877												
X0325563	BITUMINOUS BASE COURSE, SUPERPAVE, N70, 8"	SQ YD	4,861	4,861												
X0325564	BITUMINOUS BASE COURSE, SUPERPAVE, N90, 8"	SQ YD	49,877	49,877												
X0325565	BITUMINOUS BASE COURSE, SUPERPAVE, N90, 10 1/4"	SQ YD	9,791	9,791												
△ X0325041	REMOVE AND REPLACE LIGHTING UNIT IDENTIFICATION DECAL	EACH	15													15

△ SFTY-3N
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE
S. VERTHEIN	08/01/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILLY CACHE SLOUGH

SUMMARY OF QUANTITIES

SCALE: 1" = 50'
DATE: 07-21-06

DRAWN BY
CHECKED BY

△ Rev. 9-15-06
△ Rev. 9-5-06



FINAL