

SUMMARY OF QUANTITIES

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	588	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62303		(2021-922 PT2 ETC 2324.6-1P) R-11		

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE								
				ROADWAY IDOT J000	ROADWAY CDDT J000	RETAINING WALLS 5ND16-W170 Y007	39TH-47TH Y007	MWRD CULVERT X025-2A	SIGNING Y002-1C	SAFETY SFY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	764	764								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	774	774								
20101000	TEMPORARY FENCE	FOOT	35	35								
20200100	EARTH EXCAVATION	CU YD	99,934	99,934								
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	546	546								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10,782	10,782								
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	441			194	247					
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500								
20800150	TRENCH BACKFILL	CU YD	3234	3234								
20900110	POROUS GRANULAR BACKFILL	CU YD	844	844								
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	123,252	123,252								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	29,672	29,672								
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	34,170	34,170								
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	34,170	34,170								
25000210	SEEDING, CLASS 2A	ACRE	10.0	10.0								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,187	1,187								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,185	1,185								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,185	1,185								
25000750	MOWING	ACRE	13.8	13.8								
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	3.2	3.2								
25100630	EROSION CONTROL BLANKET	SQ YD	63,842	63,842								
25200200	SUPPLEMENTAL WATERING	UNIT	1,534	1,534								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30,484	30,484								
28000510	INLET FILTERS	EACH	408	408								
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	80,225	80,225								
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	44,027	44,027								
<del>31200100</del>	<del>STABILIZED SUB-BASE</del>	<del>SQ YD</del>	<del>0,300</del>	<del>0,300</del>								
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	2,333	2,333								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	211	211								

NP = NON-PARTICIPATING  
\* - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: 1"=N.T.S.  
DATE: 06/09/06

DRAWN BY: RGR  
CHECKED BY: DDM

Rev. 8-21-06 Rev.

500-01

12:46:35 PM 6/29/2006