

SUMMARY OF QUANTITIES

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	588	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62303 • (2021-922 PT2 ETC 2324.6-1P) R-11				

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE							
			TOTAL QUANTITY	ROADWAY IDOT J000	ROADWAY CDOT J000	RETAINING WALLS 51000-W978 Y007	RETAINING WALLS 39TH-47TH Y007	MWRD CULVERT X020-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F
60500105	FILLING MANHOLES	EACH	2	2								
60500205	FILLING CATCH BASINS	EACH	47	47								
60602800	CONCRETE GUTTER, TYPE B	FOOT	3,445	3,445								
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,801	1,801								
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	1,186	1,186								
60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	18,805	18,805								
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	013							013		
<del>63100046</del>	<del>TRAFFIC BARRIER TERMINAL, TYPE 2</del>	<del>EACH</del>	<del>1</del>									
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1								
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4								
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	5	5								
63200310	GUARDRAIL REMOVAL	FOOT	1,749	1,749								
63700805	CONCRETE BARRIER TRANSITION	FOOT	1132	1132								
64200105	SHOULDER RUMBLE STRIP	FOOT	60,655	60,655								
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	1334	1334								
67100100	MOBILIZATION	L SUM	1	1								
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	28,250	25,160	3,090							
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	580	364	216							
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	79,867	68,907	10,960							
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	14,613	10,612	4,001							
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	35,530	31,571	3,959							
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	4,303	4,126	177							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	63,998	46,249	17,749							
70400100	TEMPORARY CONCRETE BARRIER	FOOT	8,420	8,420								
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	31,830	27,330	4,500							
72000100	SIGN PANEL-TYPE 1	SQ FT	179	0					179			
72000200	SIGN PANEL-TYPE 2	SQ FT	280	0					280			
72000300	SIGN PANEL - TYPE 3	SQ FT	7,098						7,098			
72400200	REMOVE SIGN PANEL ASSEMBLY-TYPE B	EACH	12						12			

\* - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



Rev. 8-22-06

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: 1"=N.T.S  
DATE: 06/09/06

DRAWN BY: RGR  
CHECKED BY: DDM

S00-04

145558 PW 6/29/2006